

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1A. TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. U-013429-A
B. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR CNG Producing Company		7. UNIT AGREEMENT NAME River Bend
3. ADDRESS OF OPERATOR 705 S. Elgin, P. O. Box 2115, Tulsa, OK 74101-2115		8. FARM OR LEASE NAME RBU
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.) At surface 734' FNL & 2013' FEL NW NE At proposed prod. zone Same		9. WELL NO. 2-10D
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE 31 miles Southeast of Myton		10. FIELD AND POOL, OR WILDCAT UTELAND BUTTE Natural Buttes
15. DISTANCE FROM PROPOSED LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 734'	16. NO. OF ACRES IN LEASE 760	11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 10-T10S-R18E
17. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 4700'	18. PROPOSED DEPTH 9200	12. COUNTY OR PARISH 13. STATE Uintah Utah
19. ROTARY OR CABLE TOOLS Rotary		20. APPROX. DATE WORK WILL START July 25, 1987
21. ELEVATIONS (Show whether DF, RT, GR, etc.) 5034' GR		

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8"	24#, K-55	± 400'	Cement to surface
7-7/8"	5-1/2"	17# & 20#, N-80	±9200	Cement calc. to 4000'

Subject development well will be drilled to the proposed depth and set casing as above if producible hydrocarbons are indicated. Should the well be plugged and abandoned, it will be done in accordance with instructions from the BLM. All Conditions for Approval of Notice to Drill will be adhered to.

Exhibits Attached

- "A" Plat
- "B" Drilling Plan
- "C" Blow Out Preventor Equipment
- "D" Surface Use Plan
- "E" Access Roads
- "F" Production Facilities
- "G" Wellsite Layout

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED <u>Susan Lacy</u> TITLE <u>Engineering Technician</u> DATE <u>6-22-87</u>	
(This space for Federal or State office use)	
PERMIT NO. <u>43-047-31801</u>	APPROVAL DATE <u>7-8-87</u>
APPROVED BY _____	TITLE _____
CONDITIONS OF APPROVAL, IF ANY:	
DATE <u>7-8-87</u> BY <u>J. R. B.</u>	
WELL SPACING: <u>203</u>	


See Instructions On Reverse Side

RECEIVED
JUN 29 1987
DIVISION OF
OIL, GAS & MINING

**CNG PRODUCING CO.
WELL LOCATION PLAT
R.B.U. 2-10D**

LOCATED IN THE NW $\frac{1}{4}$ OF THE NE $\frac{1}{4}$ OF
SECTION 10, T10S, R18E, S.L.B.&M.

EXHIBIT "A"



SCALE: 1"=1000'

LEGEND & NOTES


- ◆ ORIGINAL CORNERS FOUND AND USED BY THIS SURVEY.

THE GENERAL LAND OFFICE PLAT WAS
USED FOR REFERENCE AND CALCULATIONS.

SURVEYOR'S CERTIFICATE

I hereby certify that this plat was prepared
from field notes of an actual survey
performed by me, during which the shown
monuments were found or established.

Jerry D. Allred
Jerry D. Allred, Registered Land
Surveyor, Cert. No. 3817 (Utah)



JERRY D. ALLRED & ASSOCIATES
Surveying & Engineering Consultants

121 North Center Street
P.O. Drawer C
DUCHESNE, UTAH 84021
(801) 738-5352

14 Oct '86

79-128-150

ONSHORE OIL AND GAS ORDER NO. 1

Drilling Plan

CNG Producing Company
 River Bend Unit
 RBU 2-10D
 Section 10-T10S-R18E
 734' FNL & 2013' FEL
 Uintah County, Utah

1. Estimated Tops of Important Geologic Markers

<u>Formation</u>	<u>Depth</u>	<u>SS</u>
Surface	0'	
Wasatch Tongue	4540'	+ 513
Green River Tongue	4700'	+ 353
Wasatch	4880'	+ 173
Mesaverde	8300'	-3247
Total Depth	9100'	

2. Estimated Depths of Anticipated Water, Oil, Gas or Minerals

<u>Formation</u>	<u>Depth</u>	<u>Remarks</u>
Wasatch Tongue	4540'	Oil
Green River Tongue	4700'	Oil
Wasatch	4880'	Gas
Mesaverde	8300'	Gas

3. Operators Minimum Specifications for Pressure Control

(See Exhibit "C")

Exhibit "C" is a schematic diagram of the BOPE. BOP's and choke manifold will be installed and pressure tested before drilling out casing cement plugs. BOP's and choke manifold will be tested to 3,000 psi and annular type preventers will be tested to 1,500 psi. Preventers will be a minimum 3,000 psi working pressure. Pipe rams will be operated daily and blind rams as possible.

4. Proposed Casing Program

<u>Size of Casing</u>	<u>Weight & Grade</u>	<u>Setting Depth</u>	<u>Quantity of Cement</u>
8-5/8"	24#, K-55	± 400'	Cement to surface
5-1/2"	17#, 20# N-80	± 9200'	Calculated to surface

5. Proposed Mud Program

The well is to be drilled with a salt water mud system maintaining a weight of approximately 9#/gal with 10#/gal salt water weighting materials on location sufficient to weight up for pressure control. Two percent (2%) KCl will be added and maintained from 4,000' to T.D. No chromates will be used in the drilling fluid.

6. Auxiliary Equipment to be Used

- A) Kelly Cock
- B) Full opening valve on floor with DP connection for use when kelly is not in string
- C) Pit volume indicator

7. Testing, Logging and Coring Program

A two (2) man mud logging unit will be in operation from 3,000' to T.D.

Testing: No DST's are anticipated

Coring: Sidewall cores of selected intervals

Logging: DLL-GR-Density/Neutron-Fraclog

Exact logging detail and procedures will be prepared prior to reaching logging depth.

8. Any Abnormal Pressure or Temperatures

No abnormal pressures are anticipated nor is the area known for abnormal temperatures. The formations to be penetrated do not contain H₂S gas. Maximum anticipated BHP is 4,500 psi at total depth.

9. Anticipated Starting Date and Duration of Operations

Starting Date: July 25, 1987

Duration: 30 days

BOP STACK




Exhibit "D"

ONSHORE OIL AND GAS ORDER NO. 1

Surface Use Plan

CNG Producing Company
River Bend Unit
RBU 2-10D
Section 10-T10S-R18E
734' FNL & 2013' FEL
Uintah County, Utah

The operator or their contractor will contact the Vernal District BLM, Diamond Resource Area, 48 hours prior to beginning any work on public lands.

The dirt contractor will be furnished with an approved copy of the surface use plan and any additional BLM stipulations prior to any work.

1. Existing Roads

- A. The proposed wellsite and elevation is shown on the plat, Exhibit "A". The location and existing roads are shown on Exhibit "E". There is no anticipated construction on any existing roads.
- B. The proposed wellsite is located in the River Bend Unit, approximately 31 miles southeast of Myton, Utah.

2. Access Roads to be Constructed

- A. The construction of an access road approximately 0.1 mile long will be required as shown on Exhibit "E".
- B. Construction and maintenance of roads, rehabilitation of disturbed areas and construction of pipeline routes will be in accordance with surface use standards as set forth in the booklet, "Surface Operating Standards for Oil and Gas Exploration and Development".
 - a. Width: Maximum of 30' right-of-way with road bed being 16'-18' and remainder of right-of-way to be used for barrow ditches.
 - b. Maximum Grade: 8%
 - c. Turnouts: None

- d. Drainage: Drain ditches along either side of road where necessary for drainage. Material from barrow ditch used to build crown of road.
 - e. Culverts: None
 - f. Surface Material: Native dirt
 - g. Gates, Cattle Guards, Fence Cuts: None
- C. All travel will be confined to existing access road rights-of-way.

3. Location of Existing Wells

All existing wells known in the area are shown on Exhibit "E". Wells within a one mile radius are listed below:

- | | |
|---------------------------------|---|
| A. Water Wells: | None |
| B. Abandoned Wells: | None |
| C. Temporarily Abandoned Wells: | None |
| D. Disposal Wells: | None |
| E. Drilling Wells: | None |
| F. Producing Wells: | RBU 5-11D |
| G. Shut-in Wells: | RBU 12-2D, RBU 13-2D,
RBU 14-2D, RBU 15-3D,
RBU 16-3D, RBU 2-11D,
RBU 4-11D, RBU 6-11D |
| H. Injection Wells: | None |
| I. Observation Wells: | None |

4. Location of Tank Batteries and Production Facilities

- A. The location of existing and/or proposed facilities owned or controlled by the lessee/operator within a one mile radius are shown on Exhibit "E".

- | | |
|---------------------------|------------------------|
| a. Tank Batteries: | At above shut-in wells |
| b. Production Facilities: | RBU 5-11D |
| c. Oil Gathering Lines: | None |
| d. Gas Gathering Lines: | RBU 5-11D |
| e. Injection Lines: | None |
| f. Disposal Lines: | None |

- B. It is contemplated that, in the event of production, all new facilities will be easily accommodated on the drill pad. The dimensions of the production facilities and their orientation is shown on Exhibit "F".

Location of production facilities will be per Conditions of Approval for Notice to Drill.

- C. Concrete and gravel as needed will be purchased from private sources.

- D. All permanent structures constructed or installed, including pumpjacks, will be painted a flat, non-reflective, earth tone color to match the standard environmental colors as determined by the Rocky Mountain 5 State Interagency Committee. Facilities required to comply with O.S.H.A. will be excluded.
- E. Pits will be fenced to minimize any hazard to sheep, cattle, antelope and other animals that graze the area. Flagging material will be used as needed if water or other fluid is produced.
- F. All site security guidelines identified in 43 CFR 3162.7 regulations will be adhered to.

5. Location and Type of Water Supply

Water for drilling purposes will be hauled from the Green River permit #T5975049-1283 or from the OSC #1 water well permit #54801 (49-367).

6. Source of Construction Material

Road surfacing and pad construction material will be native soil consisting of sandy-clay, sandstone and shale gathered in actual construction of the road and location. Construction materials will be located on the lease. The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3 regulations.

7. Methods of Handling Waster Disposal

- A. Drill cuttings will be buried in the reserve pit when covered.
- B. All drilling fluids will be handled in the reserve pit. Location as determined in Conditions of Approval for Notice to Drill.
- C. Should air assist be used in drilling operations a blouie pit will be necessary. The pit will be located on location and in a manner that will not create any additional surface disturbance.
- D. Any fluids produced during the testing will be collected in test tanks, water drained to the pit, and the oil saved.
- E. Sewage will be handled by portable chemical toilets.
- F. There will be no burning. Garbage and other waste material will be enclosed in a wire mesh container, and then disposed of in an approved waste disposal pit.
- G. After the rig moves out, all materials will be cleaned up and no adverse materials will be left on location. Any dangerous pit will be fenced or covered.

8. Ancilliary Facilities

No additional facilities, not described herein, are anticipated.

9. Wellsite Layout

- A. Exhibit "G" is the wellsite layout at a scale of 1" = 40'.
- B. The access to the well pad is shown on Exhibit "E".
- C. Stock piling of top soil will be per BLM conditions of Approval for Notice to Drill.
- D. Reserve pits will be fenced with a wire mesh fence and topped with at least one strand of barbed wire.

10. Plans for Restoration of Surface

- A. Upon completion of drilling, the location and surrounding area will be cleared of all debris, material, trash and junk not required for production. All trash will be hauled to a local sanitary landfill.
- B. The operator or their contractor will contact the Vernal District BLM, Diamond Mountain Resource Area, 24 hours prior to starting rehabilitation work that involves earth moving equipment and upon completion of restoration measures.
- C. Before any dirt work to restore the location takes place, the reserve pit will be completely dried and all trash (can, barrels, pipe, etc.) will be removed. The reserve pit and that portion of the location and access road not needed for production facilities will be reclaimed within a reasonable time period.
- D. All disturbed areas will be recontoured to the approximate natural contours.
- E. Prior to reseeding, the operator will consult with the Vernal District BLM for an approved seeding mixture. Then all disturbed areas, including access roads, will be scarified and left with a rough surface.
- F. Seed will be broadcast or drilled at a time specified by the BLM. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.

11. Surface and Mineral Ownership

Bureau of Land Management
Vernal District Office
Diamond Mountain Resource Area
170 South 500 East
Vernal, Utah 84078

12. Other Information

- A. If required, archaeological clearance will be submitted to the Vernal District BLM. If any cultural resources are found during construction, all work will cease and the BLM notified.
- B. There will be no deviation from this proposed drilling program without prior approval of the BLM.

13. Lessee's or Operator's Representatives

Jim Martin
Drilling Manager
CNG Producing Company
P. O. Box 2115
Tulsa, OK 74101-2115
Phone: (918) 599-3970
(918) 582-6355

or

Darwin Kulland
District Superintendent
CNG Producing Company
P. O. Box 1360
Roosevelt, UT 84066
Phone: (801) 722-4521
(801) 722-3892

14. Certification

I hereby certify that I, or the persons under my direct supervision, have inspected the proposed drillsite and access route, that I am familiar with the conditions which currently exist, that the statements made in this plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by CNG Producing Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

6/19/87
Date

Jim Martin
Jim Martin
Drilling Manager

[illegible][illegible][illegible]

EXHIBIT "E"

Sheep

Flu Knolls

Wash

Moon Bottom

Hydes Bottom

GREEN

FED. 1-26A

FED. 5-25A

FED. 11-26A

FED. 11-25A

FED. 13-25A

FED. 11-30A

FED. 13-30A

FED. 11-36A

FED. 13-36A

FED. 11-30B

FED. 13-30B

FED. 11-36B

FED. 13-36B

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97


98

99

100

[illegible][illegible][illegible]

EXHIBIT 'F'



Revised October 1, 1985

Date NOS Received 6-10-87

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator CNG Producing Company
Well Name & Number RBU 2-10D
Lease Number U-013429-A
Location NW 1/4 NE 1/4 Sec. 10 T. 10 S R. 18 E
Surface Ownership BLM

THIRTEEN POINT SURFACE USE PROGRAM:

Multipoint Requirements to Accompany APD

1. Existing Roads--describe the following and provide a legible map, labeled and showing:
 - A. Proposed wellsite as staked and access route to location, including distances from point where access route exits establish roads. (Actual staking should include two directional reference stakes.)
 - B. Route and distance from nearest town or locatable reference point, such as a highway or county road, to where well access route leaves main road.
 - C. Access road(s) to location color-coded or labeled.
 - D. Plans for improvement and/or maintenance of existing roads. (Appropriate rights-of-way for off lease roads should be attached.)
2. Planned Access Roads--describe the following and provide a map of suitable scale indicating all necessary access roads (permanent and temporary) to be constructed or reconstructed, showing:
 - A. Length - Approximately 520
 - B. Width - 30 foot right-of-way with 18 foot running surface maximum.
 - C. Maximum grades - 8°
 - D. Turnouts - None
 - E. Drainage design - Barrow Pits
 - F. Location and size of culverts and/or bridges, and brief description of any major cuts and fills - N/A
 - G. Surfacing material (source) - Native (from road and access)
 - H. Necessary gates, cattleguards, or fence cuts and/or modification to existing facilities - N/A
 - I. Access road surface ownership - BLM

(New or reconstructed roads are to be centerline-flagged at time of location staking.)

All travel will be confined to existing access road rights-of-way.

Access roads and surface disturbing activities will conform to standards outlined in the USGS Publication (1978) Surface Operating Standards for Oil and Gas Development.

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

~~Right-of-Way Application needed. If a ROW is necessary for the access road, a copy of the ROW grant shall be with the dirt contractor during the construction and thereafter kept on location with the complete copy of the approved APD.~~

~~Operators shall notify the following ROW grantees of their intent to use the existing roads and, if necessary, enter into a cooperative maintenance agreement.~~

~~_____

_____~~

~~The proposed access road shall utilize the upgraded 2-track trail approximately _____ (ft. or mile) as agreed upon during the onsite inspection. Remainder of planned access road will follow flagged route for _____.~~

~~The operator/lessee or his successor shall be responsible for all maintenance on cattleguards or gates associated with this oil and/or gas operation.~~

3. Location of Existing Wells--describe the following and provide a map or plat of all wells within a 1 mile radius of the proposed well location showing and identifying existing:

- A. Water wells
- B. Abandoned wells
- C. Temporarily abandoned wells
- D. Disposal wells
- E. Drilling wells
- F. Producing wells
- G. Shut-in wells
- H. Injection wells

4. Location of Existing and/or Proposed Facilities

A. On well pad: Show the following existing area facilities and dimensions to be utilized if the well is successfully completed for production (detail painting plans and color if applicable):

- (1) Tank batteries
- (2) Production facilities
- (3) Oil gathering lines
- (4) Gas gathering lines
- (5) Injection lines
- (6) Disposal lines
- (7) Surface pits (separate application per NTL-2B requirements)*

(Indicate if any of the above lines are buried.)

B. Off well pad: Same as above. Off lease flowlines may require rights-of-way or special use permits, check with the Area Office Realty Specialist. (Include a diagram of the proposed attendant lines, i.e., flowlines, powerlines, etc., if off well pad location.)

- (1) Proposed location and attendant lines shall be flagged off of well pad prior to archaeological clearance.
- (2) Dimensions of facilities
- (3) Construction methods and materials
- (4) Protective measures and devices to protect livestock and wildlife

Note: Operator has option of submitting information under 4A and B., after well is completed for production, by applying for approval of subsequent operations.

If a tank battery is constructed on this lease, the battery or the well pad will be surrounded by a dike of sufficient capacity to contain $1\frac{1}{2}$ times the storage capacity of the battery. The integrity of the dike must be maintained.

Tank batteries will be placed on the NE Corner of location

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rock Mountain Five State Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Slate Gray (5Y61).

5. Location and Type of Water Supply

- A. Show location and type of water supply, either by $\frac{1}{4}$, $\frac{1}{2}$ section on a map or by written description _____.
- B. State method of transporting water, and show any roads or pipelines needed.
- C. If water well is to be drilled on lease, so state. _____

*The operator will be responsible for acquiring the necessary permit to obtain water to be used for drilling activities.

6. Source of Construction Materials

- A. Show information either on map or by written description -
Native material from Access and location _____.
- B. Identify if from Federal or Indian (tribal or allotted) land.
- C. Describe where materials such as sand, gravel, stone, and soil material are to be obtained and used.

*If fill materials are needed to construct roads or well sites, proper permits must be obtained from the Surface Management Agency, unless materials are obtained from a private source.

*A minerals material application ^{XX} ~~is~~/is not) required.

7. Methods for Handling Waste Disposal

- A. Describe methods and location of proposed safe containment and disposal of each type of waste material, including:
 - (1) Cuttings
 - (2) Sewage
 - (3) Garbage (trash) and other waste material
 - (4) Salts
 - (5) Chemicals
- B. Provide a plan for eventual disposal of drilling fluids and any produced oil or water recovered during testing operations. _____

*Burning will not be allowed. All trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

*Pits are not to be located in natural drainages where a flood hazard exists or surface runoff will destroy or damage the pit walls, unless otherwise herein provided.

On BLM administered lands:

The reserve pit (shall/~~XXXXXXX~~) be lined. If deemed necessary by onsite inspection when built.

*If the pit is lined, it shall be constructed so as not to leak, break, or allow discharge.

— The bottom of the reserve pit shall not be in fill material.
would

For the following reasons the reserve pit ~~will~~ be lined:

XX. To conserve water (because of operator's request).

*If a plastic nylon reinforced liner is used it shall be torn and perforated before backfilling of the reserve pit.

— To protect the environment.

~~If the reserve pit is lined the operator will provide the BLM a chemical analysis of the fluids in the pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements prescribed by Part II, Standards of Quality for Waters of the State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.~~

— To protect the environment (without a chemical analysis).
reserve

Produced waste water will be confined to a (~~XXXXXXX~~) pit or, if deemed necessary, a storage tank for a period not to exceed 90 days after first production. During the 90-day period an application for approval of a permanent disposal method and location, along with required water analysis, will be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

On BIA administered lands:

All reserve pits ~~will~~ be lined with either native clay, commercial bentonite or plastic sufficient to prevent seepage. (If a plastic nylon reinforced liner is used, it shall be torn and perforated after the pit dries and before backfilling of the reserve pit.)

— To protect the environment.

If the reserve pit is lined the operator will provide the BLM a chemical analysis of the fluids in that pit no later than 90 days after the well completion to determine the method for final reclamation of the reserve pit. If the elemental concentrations shown by the chemical analysis exceeds the requirements prescribed by Part II, Standards of Quality for Waters of the

~~State, Wastewater Disposal Regulations, State of Utah Division of Health, the contents and liner will be removed and disposed of at an authorized disposal site.~~

~~— To protect the environment (without a chemical analysis).~~

~~Pits will be constructed so as not to leak, break, or allow discharge of liquids.~~

~~— Storage tanks will be used if drill sites are located on tribal irrigable land, flood plains, or on lands under crop production.~~

~~Produced waste water will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. During the 90 day period an application for approval of a permanent disposal method and location, along with required water analysis, will be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.~~

8. Ancillary Facilities

- A. Identify all proposed camps and airstrips on a map as to their location, and area required, and construction methods. (Camp center and airstrip centerlines to be staked on the ground.)

XX Camp facilities or airstrips will not be required.

9. Well Site Layout--provide a plat (not less than 1" = 50') showing:

- A. Cross-sections of proposed drill pad with approximate cuts and fills and the relation to topography.
- B. Location of mud tanks, reserve, blooie, and emergency pits, pipe racks, living facilities, and soil material stockpiles, etc. (Approval as used in this section means field approval of location.)
- C. Rig orientation, parking areas, and access roads, etc.

All pits will be fenced with a wire mesh fence and topped with at least one strand of barbed wire. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Any hydrocarbons on the pit will be removed from the pit as soon as possible after drilling operations are completed. Pits will be fenced and maintained until clean-up.

The fence will be constructed as prescribed in the USGS Publication (1978) Surface Operating Standards for Oil and Gas Development. Alternatives to the prescribed standards shall be submitted to the Authorized Officer for approval.

Well Site Layout: The reserve pit will be located on the: _____
NW corner of location

The stockpiled topsoil will be stored on the: _____
NE by point 6

Access to the well pad will be from the: East

— Diversion ditch(es) shall be constructed on the North side of the location (above / ~~below~~) the cut slope, draining to the East and West.

~~— Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____.~~

— ~~The drainage(s) shall be diverted around the _____ side(s) of the well pad location.~~

— ~~The reserve pit and/or pad location shall be constructed long and narrow for topographic reasons _____.~~

— The _____ corner of the well pad will be rounded off to avoid the _____.

10. Plans for Restoration of Surface

A. Provide a restoration program upon completion of operations, including:

- (1) Backfilling, leveling, recontouring, and waste disposal; segregation of topsoil from cut materials as needed
- (2) Revegetation and rehabilitation--including abandoned access roads or portions of well pads no longer needed (normally per BLM recommendations)
- (3) Proposed timetable for commencement and completion of rehabilitation operations

B. The following are provisions to be addressed in the restoration plan:

Immediately upon well completion, the location and surrounding area will be cleared of all debris, materials, trash and junk not required for production.

Before any dirt work to restore the location takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc. will be removed. The reserve pit and that portion of the location and access road not needed for production facilities/operations will be reclaimed. The reserve pit will be reclaimed within 6 months from the date of well completion.

All disturbed areas will be recontoured to the approximate natural contours.

The stockpiled topsoil will be evenly distributed over the disturbed areas.

Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface.

Seed will be broadcast or drilled at a time specified by the BLM / BIA / FS / Private Surface Owner. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage and the seed mixture will be proportionately larger (double the lbs. per acre).

An appropriate seed mixture will be determined by the BLM / BIA / FS / Private Surface Owner, either as part of the Conditions of Approval of the APD or at the time restoration activities are scheduled to begin.

All seeding will be done from September 15th until the ground freezes.

At such time as the well is plugged and abandoned the operator will submit a surface reclamation plan to the Surface Management Agency for prescribed seed mixtures and reseeding requirements.

If the seeding is unsuccessful, the lessee/operator may be required to make subsequent seedings.

On BIA administered lands:

~~Abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include: (a) reestablishing irrigation systems where applicable, (b) reestablishing soil conditions in irrigated fields in such a way as to insure cultivation and harvesting of crops and, (c) insuring revegetation of the disturbed areas to the specifications of the Ute Indian Tribe or the BIA at the time of abandonment.~~

~~The operator will submit a plan of controlling noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. A list of noxious weeds can be obtained from the appropriate county extension office.~~

The BLM recommends the following procedure for reclamation:

Compacted areas of the well pad should be plowed or ripped to a depth of 12" before reseeding. Seeding should be done with a disc-type drill to ten inches apart. The seed should be planted between one-half inch deep and three quarter inch deep. A drag, packer or roller may be used to insure uniform coverage of the seed, and adequate compaction. Drilling of the seed should be done on the contour where possible. Where slopes are too steep for contour drilling a "cyclone" hand-seeder or similar broadcast seeder should be used, using twice the recommended seed per acre. Seed should then be covered to a depth described above by what-ever means is practical.

11. Surface Ownership: BLM

Provide the surface ownership (Federal, Indian, State or private) at the well location, and for all lands crossed by roads which are to be constructed or upgraded.

Where the surface of the well site is privately owned, the operator shall provide the name, address, and, if known, telephone number of the surface owner.

12. Other Additional Information

The BLM recommends a general description of:

- A. Topography, soil characteristics, geologic features, flora and fauna
- B. Other surface-use activities and surface ownership of all involved lands
- C. Proximity of water, occupied dwellings, archaeological, historical or cultural sites

A cultural resource clearance will be required before any construction begins on Federal and Indian lands. However, historic and cultural resource work shall be undertaken only with the written consent of a private surface owner. If the private surface owner refuses entry for that purpose, the lessee or operator shall use its best efforts to conduct its approved operations in a manner that avoids adverse effects on any properties which are listed, or may be eligible for listing, in the NRHP.

If, during operations, any archaeological or historical sites, or any object of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites are to be suspended and the discovery reported promptly to the Surface Management Agency.

On BLM administered land, it is required that a proposed use of pesticide, herbicide or other possible hazardous chemicals shall be cleared for use prior to application.

On BIA administered land:

Operator's employees, including subcontractors, will not gather firewood along roads constructed by operators. If wood cutting is required, a permit will be obtained from the Forestry Department of the BIA pursuant to 25 CFR 169.13 "Assessed Damages Incident to Right-of-Way Authorization". All operators, sub-contractors, vendors and their employees or agents may not disturb saleable timber (including firewood) without a duly granted wood permit from the BIA Forester.

If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved rights-of-way will be obtained from the BIA before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

All roads constructed by operators on the Uintah and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. They will state: (a) that the land is owned by the Ute Indian Tribe, (b) the name of the operator, (c) that firearms are prohibited to all non-Ute Tribal members, (d) that permits must be obtained from the BIA before cutting firewood or other timber products and (e) only authorized personnel permitted.

All well site locations on the Uintah and Ouray Indian Reservation will have an appropriate sign indicating the name of the operator, the lease serial number, the well name and number, the survey description of the well (either footages or the quarter-quarter section, the section, township, and range).

Additional Surface Stipulations for BLM, BIA, FS, DWR, or Private Surface Lands:

The operator or his contractor shall contact the BLM and BIA Offices at (801) 789-1362 (BLM) and (801) 722-2406 (BIA) between 24 and 48 hours prior to construction activities. Contact Tim O'Brien w/ BLM.

- ___ The BLM and BIA Offices shall be notified upon site completion prior to moving on the drilling rig.
- ___ No construction or drilling activities shall be conducted between November 1 thru March 1 because of bald and golden eagle winter habitat areas.
- ___ No construction or drilling activities shall be conducted between _____ and _____ because of big game habitat areas.
- ___ No construction or exploration activity will be permitted _____ through _____ due to the presence of an active raptor nest or eyrie.
- ___ No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.
- ___ No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.
- ___ There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).
- ___ No cottonwood trees will be removed or damaged.
- ___ A _____ ft. tree screen or vegetative buffer shall be left on the _____ side(s) of the well location, to minimize visual impacts and for watershed protection.
- ___ All rock art sites will be avoided by construction/drilling/ maintenance activities by a minimum of 500 feet.
- ___ No construction or drilling activities shall be conducted between _____ and _____ because of the possible presence of Threatened and Endangered plant species.
- ___ Overhead flagging will be installed on pits to protect waterfowl and birds.
- ___ Bloovey pit will be located east of and seperate from reserve pit minimum 100' from rig.
- ___ When the drilling rig is selected and prior to construction, the BLM will be contacted to see if shortening of location is possible.
- ___ Dike drainage of SW corner of location to form a livestock reservoir.

Fence Stipulation:

~~Each existing fence to be crossed by the right-of-way shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguard (shall/shall not) be permanently mounted on concrete bases. Prior to crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/ her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.~~

Grazing Permittee _____

Address _____ Phone No. _____

Note: If the land is privately owned, these surface stipulations may be varied to comply with the operator - land owner agreement.

13. Lessee's or Operators Representative and Certification

Representative

Name: _____

Address: _____

Phone No. _____

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his sub-contractors. A copy of these conditions will be furnished the field representative to insure compliance.

The dirt contractor will be provided with an approved copy of the Surface Use Plan from the APD.

This drilling permit will be valid for a period of one year from the date of approval. After permit termination, a new application will be filed for approval for any future operations.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and, that the work associated with the operations proposed here will be performed by CNG Producing

Company
and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

6-22-87

Date

Jim Martin, Manager, Drilling

Name and Title


Onsite Date: _____

Participants on Joint Inspection

Darwin Kolland CNG


MAX FARNSWORTH CNG

Timothy P. O'Brien BLM



Notes


THIS LOCATION IS LOCATED ON THE SOUTH SLOPE OF A LOW HILL WITH GENERAL DRAINAGE EASTERLY TOWARD THE GREEN RIVER.
THE SOIL IS SHALE AND WEATHERED SANDSTONE.



APPROXIMATE QUANTITIES

CUT: 22,100 Cu. Yds.

FILL: 12,800 Cu. Yds.



KEYWAY A—A



JERRY D. ALLRED & ASSOCIATES
Surveying & Engineering Consultants

121 North Center Street
P.O. Drawer C
DUCESNE, UTAH 84021
(801) 738-8352


071331

OPERATOR C. N. G. Producing Company DATE 7-2-87
 WELL NAME R. B. U. # 2-10D
 SEC NW/NE 10 T 10S R 18E COUNTY Uintah


43-047-31801
API NUMBER

Fed.
TYPE OF LEASE

CHECK OFF:



PLAT




BOND

NEAREST
WELL

LEASE



FIELD


POTASH OR
OIL SHALE

PROCESSING COMMENTS:

Unit Well - Verbal approval of P.O.D. by Jereen 7/7/87
Water α - #49-367

APPROVAL LETTER:

SPACING:



203

River Bend
UNIT



302



CAUSE NO. & DATE



302.1

STIPULATIONS:

0218T



STATE OF UTAH
NATURAL RESOURCES
Oil, Gas & Mining

Norman H. Bangerter, Governor
Dee C. Hansen, Executive Director
Dianne R. Nielson, Ph.D., Division Director

355 W. North Temple • 3 Triad Center • Suite 350 • Salt Lake City, UT 84180-1203 • 801-538-5340

July 8, 1987

CNG Producing Company
705 S. Elgin
P. O. Box 2115
Tulsa, Oklahoma 74101-2115

Gentlemen:

Re: River Bend Unit 2-10D - NW NE Sec. 10, T. 10S, R. 18E
734' FNL, 2013' FEL - Uintah County, Utah

Approval to drill the referenced well is hereby granted in accordance with Section 40-6-18, Utah Code Annotated, as amended 1983; and predicated on Rule 203, Oil and Gas Conservation General Rules.

In addition, the following actions are necessary to fully comply with this approval:

1. Spudding notification to the Division within 24 hours after drilling operations commence.
2. All well operators are responsible for sending an Entity Action Form to the Division of Oil, Gas and Mining within five working days of the time that a new well is spudded or a change in operations or interests necessitates a change in Entity status.
3. Submittal to the Division of completed Form OGC-8-X, Report of Water Encountered During Drilling.
4. Prompt notification to the Division should you determine that it is necessary to plug and abandon this well. Notify John R. Baza, Petroleum Engineer, (Office) (801) 538-5340, (Home) 298-7695, or R. J. Firth, Associate Director, (Home) 571-6068.
5. Compliance with the requirements and regulations of Rule 311.3, Associated Gas Flaring, Oil and Gas Conservation General Rules.

Page 2
CNG Producing Company
River Bend Unit 2-100
July 8, 1987

6. Prior to commencement of the proposed drilling operations, plans for toilet facilities and the disposal of sanitary waste at the drill site shall be submitted to the local health department having jurisdiction. Any such drilling operations and any subsequent well operations must be conducted in accordance with applicable state and local health department regulations. A list of all local health departments and copies of applicable regulations are available from the Division of Environmental Health, Bureau of General Sanitation, telephone (801) 533-6163.
7. This approval shall expire one (1) year after date of issuance unless substantial and continuous operation is underway or an application for an extension is made prior to the approval expiration date.

The API number assigned to this well is 43-047-31801.

Sincerely,



R. J. Firth
Associate Director, Oil & Gas

as
Enclosures
cc: Branch of Fluid Minerals
D. R. Nielson
8159T

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/>			5. LEASE DESIGNATION AND SERIAL NO. U-013429-A	
b. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>			6. IF INDIAN, ALLOTTEE OR TRIBE NAME 071719	
2. NAME OF OPERATOR CNG Producing Company			7. UNIT AGREEMENT NAME River Bend	
3. ADDRESS OF OPERATOR 705 S. Elgin, P. O. Box 2115, Tulsa, OK 74101-2115			8. FARM OR LEASE NAME RBU	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.) At surface 734' FNL & 2013' FEL NW NE At proposed prod. zone Same			9. WELL NO. 2-10D	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* 31 miles Southeast of Myton			10. FIELD AND POOL, OR WILDCAT Natural Buttes	
15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any) 734'			11. SEC. T., R., M., OR BLE. AND SURVEY OR AREA Sec. 10-T10S-R18E	
16. NO. OF ACRES IN LEASE 760			12. COUNTY OR PARISH 13. STATE Utah Utah	
17. DISTANCE FROM PROPOSED* LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 4700'			14. NO. OF ACRES ASSIGNED TO THIS WELL 80	
18. PROPOSED DEPTH 9200			15. ROTARY OR CABLE TOOLS Rotary	
21. ELEVATIONS (Show whether DF, RT, GR, etc.) 5034' GR			22. APPROX. DATE WORK WILL START* July 25, 1987	

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8"	24#, K-55	± 400'	Cement to surface
7-7/8"	5-1/2"	17# & 20#, N-80	±9200	Cement calc. to 4000'

Subject development well will be drilled to the proposed depth and set casing as above if producible hydrocarbons are indicated. Should the well be plugged and abandoned, it will be done in accordance with instructions from the BLM. All Conditions for Approval of Notice to Drill will be adhered to.

Exhibits Attached

- "A" Plat
- "B" Drilling Plan
- "C" Blow Out Preventor Equipment
- "D" Surface Use Plan
- "E" Access Roads
- "F" Production Facilities
- "G" Wellsite Layout

RECEIVED
JUL 13 1987

DIVISION OF
OIL, GAS & MINING

JUN 24 1987

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED <u>Susan Laury</u> TITLE <u>Engineering Technician</u> DATE <u>6-22-87</u>	
(This space for Federal or State office use)	
PERMIT NO. <u>43047-31801</u>	APPROVAL DATE
APPROVED BY <u>William H. Henson</u> TITLE <u>Acting District Manager</u> DATE <u>7-7-87</u>	
CONDITIONS OF APPROVAL, IF ANY.	

Exp.
5-9-87

TEMPORARY
FILING FOR WATER IN THE
STATE OF UTAH 030718

file

APPLICATION TO APPROPRIATE WATER

Rec. by ga
Fee Paid \$ 15.00 20008
Platted _____
Microfilmed _____
Roll # _____

For the purpose of acquiring the right to use a portion of the unappropriated water of the State of Utah, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.

WATER USER CLAIM NO. 47 - 1760

APPLICATION NO. T61598

1. PRIORITY OF RIGHT: February 28, 1986

FILING DATE: February 28, 1986

2. OWNER INFORMATION

Name: CNG Producing Company

Address: P.O. Box 1360, Roosevelt, UT 84066

The land is not owned by the applicant(s), see explanatory.

3. QUANTITY OF WATER: 15.0 acre feet (Ac. Ft.)

4. SOURCE: Green River DRAINAGE: Nine Mile Creek

POINT(S) OF DIVERSION:

COUNTY: Uintah

(1) S. 1700 feet, W. 1200 feet, from the NE Corner of Section 19,
Township 10 S, Range 19 E, SLB&M

Description of Diverting Works: Pump and tank trucks

COMMON DESCRIPTION: 11 mi. SW of Ouray, Utah

5. NATURE AND PERIOD OF USE

Oil Exploration From March 15 to March 15.

6. PURPOSE AND EXTENT OF USE

Oil Exploratio: Drilling and servicing of oil and/or gas wells.

7. PLACE OF USE

The water is used in all or parts of each of the following legal subdivisions.

TOWN	RANGE	SEC	North East Quarter				North West Quarter				South West Quarter				South East Quarter			
			NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$
10 S	18 E	09	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
✓ 10 S	18 E	10	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	11	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	12	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	15	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	16	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
10 S	18 E	19	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X

All locations in Salt Lake Base and Meridian

RIVER BEND UNIT 2-100 43-047-31801 POW

EXPLANATORY

The land this water is used on is BLM land which is leased by CNG Producing Company.

The water is to be used for drilling and servicing of oil and/or gas wells.

TEMPORARY

Appropriate

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Company CNG Producing Co. Well No. 2-10 D

Location Sec. 10 T.10S., R.18E., Lease No. U-013429-A

Onsite Inspection Date _____

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Order No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report all water shows and water-bearing sands encountered to Wayne Svejnoha of this office. Copies of State of Utah form OGC-8-X will be acceptable. If noticeable water flows are encountered, submit samples to this office along with any water analyses conducted by the operator.

All fresh water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

All BOPE and testing procedures will be consistent with API RP 53. Pressure tests will be conducted before drilling out from under all casing strings which are set and cemented in place. Blowout preventer controls will be installed prior to drilling the surface casing plug and will remain in use until the well is completed or abandoned. Preventers will be inspected and operated at least daily to ensure good mechanical working order, and this inspection recorded on the daily drilling report. Preventers will be pressure tested before drilling casing cement plugs.

The District Office shall be notified, with sufficient lead time, in order to have a BLM representative on location during pressure testing.

3. Casing Program and Auxiliary Equipment

If production casing is run and cemented, a cement bond log shall be run to verify cement top and percentage bond. Copies of this and all other logs shall be submitted to this office.

The District Office shall be notified, with sufficient lead time, in order to have a BLM representative on location while running all casing strings and cementing.

4. Mud Program and Circulating Medium

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the authorized officer (AO).

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The spud date will be reported orally to the AO within 48 hours after spudding. If the spudding occurs on a weekend or holiday, the report will be submitted on the following regular work day. The oral report will be followed up with a Sundry Notice.

In accordance with Onshore Oil and Gas Order No. 1, this well will be reported on Form 3160-6 "Monthly Report of Operations", starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report will be filed, in duplicate, to the Vernal BLM District Office, 170 South 500 East, Vernal, Utah 84078.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than 5 days following the date on which the well is placed on production.

Pursuant to NTL-2B, with the approval of a District Engineer, produced water may be temporarily disposed of into unlined pits for a period of up to 90 days. During the period so authorized, an application for approval of the permanent disposal method, along with the required water analysis and other information, must be submitted to the District Engineer.

Pursuant to NTL-4A, lessees or operators are authorized to vent/flare gas during initial well evaluation tests, not exceeding a period of 30 days or the production of 50 MMCF of gas, whichever occurs first. An application must be filed with the District Engineer and approval received, for any venting/flaring of gas beyond the initial 30 day or authorized test period.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in 43 CFR 3162.7 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

A first production conference will be scheduled within 15 days after receipt of the first production notice.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within 30 days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

Pursuant to Onshore Oil and Gas Order No. 1, lessees and operators have the responsibility to see that their exploration, development, production, and construction operations are conducted in a manner which conforms with applicable Federal laws and regulations and with State and local laws and regulations to the extent that such State and local laws are applicable to operations on Federal or Indian lands.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All site security guidelines identified in 43 CFR 3162.7 regulations will be adhered to.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with the API standards for liquid hydrocarbons and the AGA standard for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or work-over program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not

later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

In the event after-hour approvals are necessary, please contact one of the following individuals:

Craig M. Hansen	(801) 247-2318
Assistant District Manager	
for Minerals	

Gerald E. Kenczka	(801) 781-1190
Petroleum Engineer	

R. Allen McKee	(801) 781-1368
Petroleum Engineer	

Revised October 1, 1985

Date NOS Received 06/10/87

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

Company/Operator CNG Producing Company

Well Name & Number RBU No. 2-10D

Lease Number U-013429-A

Location NW ¼ NE ¼ Sec. 10 T. 10S., R. 18E.

Surface Ownership BLM

THIRTEEN POINT SURFACE USE PROGRAM:

Multipoint Requirements to Accompany APD

1. Planned Access Roads

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right-of-way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

2. Location of Existing and/or Proposed Facilities

If a tank battery is constructed on this lease, the battery or the well pad will be surrounded by a dike of sufficient capacity to contain $1\frac{1}{2}$ times the storage capacity of the battery. The integrity of the dike must be maintained.

Tank batteries will be placed on the northeast side of location.

The required paint color is slate gray (5Y 6/1).

On BLM administered lands:

The reserve pit shall be lined if necessary, BLM will determine when built.

If the pit is lined, it shall be constructed so as not to leak, break, or allow discharge.

Produced waste water will be confined to the reserve pit or, if deemed necessary, a storage tank for a period not to exceed 90 days after first production. During the 90-day period an application for approval of a permanent disposal method and location, along with required water analysis, will be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

3. Well Site Layout

All pits will be fenced with a wire mesh fence and topped with at least one strand of barbed wire. The reserve pit fencing will be on three

sides during drilling operations and on the fourth side when the rig moves off the location. Any hydrocarbons on the pit will be removed from the pit as soon as possible after drilling operations are completed. Pits will be fenced and maintained until clean-up.

The reserve pit will be located on the northwest side of the location.

The stockpiled topsoil will be stored on the northeast side by point 6.

Access to the well pad will be from the east side of location.

Diversion ditches shall be constructed on the north side of the location above the cut slope, draining to the east and west.

4. Plans for Restoration of Surface

A. Provide a restoration program upon completion of operations, including:

- (1) Backfilling, leveling, recontouring, and waste disposal; segregation of topsoil from cut materials as needed
- (2) Revegetation and rehabilitation--including abandoned access roads or portions of well pads no longer needed (normally per BLM recommendations)
- (3) Proposed timetable for commencement and completion of rehabilitation operations

B. The following are provisions to be addressed in the restoration plan:

The reserve pit will be reclaimed within 6 months from the date of well completion.

The stockpiled topsoil will be evenly distributed over the disturbed areas.

All seeding will be done from September 15 until the ground freezes.

If the seeding is unsuccessful, the lessee/operator may be required to make subsequent seedings.

On BLM administered land, it is required that a proposed use of pesticide, herbicide or other possible hazardous chemicals shall be cleared for use prior to application.

Additional Surface Stipulations for BLM Surface Lands

Bloolie pit will be located east of and separate from the reserve pit a minimum of 100 feet from the rig.

Once the rig is selected and prior to construction of location, the BLM will be contacted if it would be possible to shorten the location.

Dike the drainage off the southwest corner to form a reservoir.

When the location is built, all dirt and disturbance to the toe of the fill slope will be contained within the outside perimeter of the staked location.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

This drilling permit will be valid for a period of one year from the date of approval. After permit termination, a new application will be filed for approval for any future operations.

Onsite Date: June 22, 1987

Participants on Joint Inspection

Timothy P. O'Brien

Bureau of Land Management

Darwin Kulland

CNG Producing Co.

072901

DIVISION OF OIL, GAS AND MINING

SPODDING INFORMATION

API #43-047-31801

NAME OF COMPANY: CNG PRODUCING COMPANYWELL NAME: RIVER BEND UNIT 2-10DSECTION NW NE 10 TOWNSHIP 10S RANGE 18E COUNTY UintahDRILLING CONTRACTOR Leon RossRIG # SPUDDED: DATE 7-27-87TIME 9:30 AMHow Dry Hole SpudderDRILLING WILL COMMENCE 7-29-87 - Olsen, Rig #2REPORTED BY ShirleyTELEPHONE # 722-4521DATE 7-28-87 SIGNED AS

UNIT STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLI 3*
(Other instructions on re-
verse side)

Form approved.
Budget Bureau No. 1004-0135
Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. U-013429-A	
2. NAME OF OPERATOR CNG Producing Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME 082102	
3. ADDRESS OF OPERATOR P.O. Box 1360; Roosevelt, Utah 84066		7. UNIT AGREEMENT NAME River Bend Unit	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 743' FNL & 2013' FEL NW, NE		8. FARM OR LEASE NAME RBU	
14. PERMIT NO. 43-047-31801		9. WELL NO. RBU 2-10D	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 5034' GR		10. FIELD AND POOL, OR WILDCAT Uteland Buttes	
		11. SEC., T., R., M., OR BLK. AND SUBVY OR AREA Sec. 10, T 10 S, R 18 E	
		12. COUNTY OR PARISH Uintah	
		13. STATE Utah	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) Spud surface hole	(Other) <input checked="" type="checkbox"/>

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

The RBU 2-10D was Spudded at 9:30 a.m. on July 27, 1987. Leon Ross Drilling (dry hole driller) drilled 400' of 12-1/4" hole then ran shoe, 9 joints of 8-5/8" 24# casing with shoe at 399', and 3 centralizers.

BJ Titan cemented to surface using 210 sacks of class "G" cement with 53# of cello-flake.

18. I hereby certify that the foregoing is true and correct
SIGNED Darwin Kulland TITLE District Superintendent DATE August 5, 1987

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ Other _____
b. TYPE OF COMPLETION: NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other _____

2. NAME OF OPERATOR

CNG Producing Co. -Tulsa Division

3. ADDRESS OF OPERATOR

Box 2115, Tulsa, OK 74101-2115

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 734' FNL & 2,013' FEL, NW/4 NE/4

At top prod. interval reported below

At total depth

DIVISION OF
OIL, GAS & MINING

14. PERMIT NO.

43-047-31801

DATE ISSUED

7/7/87

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

Sec. 10-T10S-R10E

12. COUNTY OR PARISH

Utah

13. STATE

Utah

15. DATE SPUDDED

7/27/87

16. DATE T.D. REACHED

8/6/87

17. DATE COMPL. (Ready to prod.)

11/17/87

18. ELEVATIONS (DF, RKB, RT, OR, ETC.)*

5,034 GR; 5,049 KB

20. TOTAL DEPTH, MD & TVD

5,100 (MD)

21. PLUG, BACK T.D., MD & TVD

5,960 (MD)

22. IF MULTIPLE COMPL., HOW MANY*

23. INTERVALS DRILLED BY

Surface-TD

ROTARY TOOLS

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*

Wasatch Tongue, 4,366-4,386 (MD)

Green River Tongue, 4,890-4,898 (MD)

25. WAS DIRECTIONAL SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

CDL-CNL, DLL-MSFL, CBL/GR-CCL

LASERLOG 9-15-87, 1-22-88

27. WAS WELL CORRED

No

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8-5/8	24	414	12 1/4"	210 sxs Class G	None
5 1/2	15.5, 17	5,082	7-7/8"	398 sxs HiLift, 1016 sxs D42, 511 sxs 50:50 Poz	None

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8	4,420	Anchor @ 4,355

31. PERFORATION RECORD (Interval, size and number)

Wasatch Tongue, 4,366'-4,386', 0.5", 4 SPF
Green River Tongue, 4,890'-4,898', 0.5", 4 SPF

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
4,890-4,898	500 gals 7 1/2% HCl acid
4,890-4898	14,000 gal N2 foam, 12,000# 20/40s
4,366-4,386	2,772 gals 2% KCl wtr, 6,000# 12/20 s
4,366-4,386	16,918 gal N2 foam, 20,000# 20/40s, 10,000# 10/20s

33. PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
9/26/87		Pumping, 1½" BHD pump				Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
12/8/87	24		→	67	TSTM	75	-
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
-	0	→	67	TSTM	75	34.9	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Used for fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

2 sets of logs

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Susan Lany

TITLE

Engr. Tech.

DATE

1/19/88

*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, flowing and shut-in pressures, and recoveries):

38. GEOLOGIC MARKERS				
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME
				MEAS. DEPTH
				TRUE VERT. DEPTH
'K' Zone	3,866	4,342	3 sands > 13% Ø, 25 net feet sand, oil shows on pit. SMC's taken	Wasatch Tongue
Wasatch Tongue	4,342	4,733	10% Ø, 13 net feet sand, SMC's bleeding oil.	Green River Tongue
Green River Ton. #9	4,733	4,928	13.5% Ø, 8 net feet sand, F1 on core, limited	Wasatch

From the desk of . . .

Susan Lacy

2-3-88

DATE

To: BLM - Vernal
State of Utah
Well file

Attached is a corrected copy
of the RBU 2-10 D Completion
Report. Please note the
Corrected PBTD.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

(Other instructions on reverse side)

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

5. LEASE DESIGNATION AND SERIAL NO.

U-013429-A *POW-GR-WS*
021208

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

River Bend

8. FARM OR LEASE NAME

RBU

9. WELL NO.

RBU 2-10D

10. FIELD AND POOL, OR WILDCAT

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

Sec. 10-T10S-R10E

12. COUNTY OR PARISH

Utah

13. STATE

Utah

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐

b. TYPE OF COMPLETION:

NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. REVR. ☐

2. NAME OF OPERATOR

CNG Producing Co. -Tulsa Division

3. ADDRESS OF OPERATOR

Box 2115, Tulsa, OK 74101-2115

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 734' FNL & 2,013' FEL, NW/4 NE/4

At top prod. interval reported below

At total depth

14. PERMIT NO.

43047-31801

DATE ISSUED

7/7/87

15. DATE SPUDDED

7/27/87

16. DATE T.D. REACHED

8/6/87

17. DATE COMPL. (Ready to prod.)

11/17/87

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*

5,034 GR; 5,049 KB

19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD

5,100 (MD)

21. PLUG, BACK T.D., MD & TVD

4,960 (MD)

22. IF MULTIPLE COMPL., HOW MANY*

23. INTERVALS DRILLED BY

Rotary Tools

Cable Tools

Surface-TD

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*

Wasatch Tongue, 4,366-4,386 (MD)

Green River Tongue, 4,890-4,898 (MD)

25. WAS DIRECTIONAL SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

CDL-CNL, DLL-MSFL, CBL/GR-CCL

27. WAS WELL CORRED

No

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8-5/8	24	414	12 1/4"	210 sxs Class G	None
5 1/2	15.5, 17	5,082	7-7/8"	398 sxs HiLift, 1016 sxs D42, 511 sxs 50:50 Poz	None

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8	4,420	Anchor @ 4,355

31. PERFORATION RECORD (Interval, size and number)

Wasatch Tongue, 4,366'-4,386', 0.5", 4 SPF
Green River Tongue, 4,890'-4,898', 0.5", 4 SPF

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
4,890-4,898	500 gals 7 1/2% HCl acid
4,890-4898	14,000 gal N2 foam, 12,000# 20/40
4,366-4,386	2,772 gals 2% KCl wtr, 8,000# 12/20
4,366-4,386	16,918 gal N2 foam, 20,000# 20/40, 10,000# 10/20

33.* PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
9/26/87		Pumping, 1½" BHD pump				Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BSL.	GAS—MCF.	WATER—BSL.	GAS-OIL RATIO
12/8/87	24		→	67	TSTM	75	-
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BSL.	GAS—MCF.	WATER—BSL.	OIL GRAVITY-API (CORR.)	
-	0	→	67	TSTM	75	34.9	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Used for fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

2 sets of logs

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Susan Lany

TITLE

Engr. Tech.

DATE

1/19/88

*(See Instructions and Spaces for Additional Data on Reverse Side)


37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):							38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP				
					MEAS. DEPTH	TRUE VERT. DEPTH			
'K' Zone	3,866	4,342	3 sands > 13% Ø, 25 net feet sand, oil shows on pit. SMC's taken	Wasatch Tongue	4,342				
Wasatch Tongue	4,342	4,733	10% Ø, 13 net feet sand, SMC's bleeding oil.	Green River Tongue	4,733				
Green River Ton. #9	4,733	4,928	13.5% Ø, 8 net feet sand, FI on core, limited	Wasatch	4,928				

21801

RBU 2-107 Sec 10, T8 S0, R18E Chubly 5/11/89

L N



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Le Designation and Serial Number

U-013429-A

7. Indian Allottee or Tribe Name

8. Unit or Communization Agreement

River Bend Unit

9. Well Name and Number

RBU 2-10D

10. API Well Number

43-047-31801

11. Field and Pool, or Wildcat

Natural Buttes

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other (specify)

2. Name of Operator

CNG Producing Company

3. Address of Operator

1450 Poydras St., New Orleans, LA 70112-6000

4. Telephone Number

(504) 593-7260

5. Location of Well

Footage : 734' FNL & 2,103' FEL
QQ, SEC., T., R., M.: NW NE of Sec. 10-T10S-R18E

County : Uintah
State : UTAH

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

☐ Abandonment ☐ New Construction
☐ Casing Repair ☐ Pull or Alter Casing
☐ Change of Plans ☐ Recompletion
☐ Conversion to Injection ☐ Shoot or Acidize
☐ Fracture Treat ☐ Vent or Flare
☐ Multiple Completion ☐ Water Shut-Off
☐ Other _____

Approximate Date Work Will Start

SUBSEQUENT REPORT
(Submit Original Form Only)

☐ Abandonment * ☐ New Construction
☐ Casing Repair ☐ Pull or Alter Casing
☐ Change of Plans ☐ Shoot or Acidize
☐ Conversion to Injection ☐ Vent or Flare
☐ Fracture Treat ☐ Water Shut-Off
☒ Other Annual Status Report

Date of Work Completion

Report results of Multiple Completions and Recompletions to
different reservoirs on WELL COMPLETION OR RECOMPLETION
AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

STATUS OF WELL

Shut-in

EXPLANATION FOR STATUS OF WELL

Under evaluation

FUTURE PLANS

Possible workover or recompletion

RECEIVED

FEB 06 1992

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name & Signature

W. Scot Childress
W. Scot Childress

Title

Supervisor, Prod. Engineering

Date January 31, 1992

(State Use Only)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to deepen or re-enter an
abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-013429-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 583-7000	7. If Unit or CA/ Agreement, Name and/or No. RIVERBEND
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 734' FNL & 2,013' FEL of Sec. 10-T10S-R18E		8. Well Name and No. RBU 2-10D
		9. API Well No. 43-047-31801
		10. Field and Pool, or Exploratory Area
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>REPORT OF OPERATIONS</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)


SUMMARY OF OPERATIONS FOR RBU 2-10D

Assigned 3-3-98
Rig up rig and equipment. Rig up hot oil truck to tubing and pump out flowline. Try to pressure up tubing. Will not pressure test. Pull up on rods and pump was unseated. Flush rods with 40 bbls of production water at 270°. Pull out of hole with rods and pump #53. Found plunger stuck on pump. Cups were bed also. Flush tubing with 20 bbls of production water at 270°. Trip in hole with pump #24, pony rods, rods, polish rods with liner. Seat pump. Fill tubing and pressure test tubing to 500 PSI. Held good. Put well on production.

14. I hereby certify that the forgoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA		Title COORDINATOR, REGULATORY REPORTS	
Signature <i>Susan H. Sachitana</i>		Date 980317	
THIS SPACE FOR FEDERAL OR STATE OFFICE USE			
Approved by		Title	Date <i>WTC 12-23-98</i> <i>PSK</i>
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number

U-013429-A

7. Indian Allottee or Tribe Name

8. Unit or Communization Agreement

River Bend Unit

9. Well Name and Number

RBU 2-10D

10. API Well Number

43-047-31801

11. Field and Pool, or Wildcat

Natural Buttes

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new well, deepen existing wells, or to reenter plugged and abandoned wells.

Use APPLICATION FOR PERMIT - for such proposals

1. Type of Well

Oil
WellGas
Well

Other (specify)

2. Name of Operator

CNG PRODUCING COMPANY

3. Address of Operator

1450 POYDRAS ST., NEW ORLEANS, LA 70112-6000

4. Telephone Number

(504) 593-7260

5. Location of Well

Footage: 734' FNL & 2,103' FEL

QQ, SEC., T., R., M.: NW NE of Sec. 10-T10S-R18E

County : UINTAH

State : UTAH

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)



Abandonment



Casing Repair



Change of Plans



Conversion to Injection



Fracture Treat



Multiple Completion



Other



New Construction



Pull or Alter Casing



Recompletion



Shoot or Acidize



Vent or Flare



Water Shut-Off

Approximate Date Work Will Start

SUBSEQUENT REPORT
(Submit Original Form Only)



Abandonment *



Casing Repair



Change of Plans



Conversion to Injection



Fracture Treat



Other



New Construction



Pull or Alter Casing



Shoot or Acidize



Vent or Flare



Water Shut-Off

ANNUAL STATUS REPORT

Date of Work Completion

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

STATUS OF WELL


Shut-in

EXPLANATION FOR STATUS OF WELL

Under evaluation

FUTURE PLANS

Evaluating subsurface equipment repair



14. I hereby certify that the foregoing is true and correct

Name & Signature

Ralph Hamrick / zhs
Ralph Hamrick

Title Production Engineer

Date

February 12, 1999

(State Use Only)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
EXPIRES: July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instruction on reverse side

1. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-013429-A
2. Name of Operator CNG PRODUCING COMPANY		6. If Indian, Allottee or Tribe Name
3a. Address 1450 POYDRAS ST, NEW ORLEANS, LA 70112-6000	3b. Phone No. (include area code) (504) 593-7000	7. If Unit or CAI Agreement, Name and/or No. RIVERBEND
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 734' FNL & 2,013' FEL of Sec. 10-T10S-R18E		8. Well Name and No. RBU 2-10D
		9. API Well No. 43-047-31801
		10. Field and Pool, or Exploratory Area
		11. County or Parish, State UINTAH, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandonment	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof.

If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones.

Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation have been completed, and the operator has determined that the site is ready for final inspection.)

Water produced from the above referenced well will be held in tanks until there is enough water to be hauled by a water truck. The water truck will then dispose of the water at Ace Water Disposal facility.



14. I hereby certify that the foregoing is true and correct Name (Printed/Typed) SUSAN H. SACHITANA	Title REGULATORY REPORTS ADMINISTRATOR
Signature <i>Susan H. Sachitana</i>	Date 990304

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001 - Whoever knowingly and willfully makes to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

COPY SENT TO OPERATOR
Date: 3-10-99
Initials: CHA



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
U-01470-A et al
(UT-932)

JUN 2 2000

NOTICE

Dominion Exploration & Production, Inc. : Oil and Gas Leases
1450 Poydras Street :
New Orleans, LA 70112-6000 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the change of name of CNG Producing Company to Dominion Exploration & Production, Inc. on Federal oil and gas leases.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from your list of leases and a list of leases obtained from our automated records system. We have not abstracted the lease files to determine if the entity affected by the name change holds an interest in the leases identified nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interests. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

The following lease on your list is closed on the records of this office: U-029277.

Due to the name change, the name of the principal on the bond is required to be changed from CNG Producing Company to Dominion Exploration & Production, Inc. on Bond No. 524 7050 (BLM Bond No. WY1898). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name should be furnished to the Wyoming State Office.

/s/ Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure
Exhibit of Leases

RECEIVED

JUN 05 2000

DIVISION OF
OIL, GAS AND MINERAL
REVENUE

cc: Wyoming State Office
New Mexico State Office
Moab Field Office
Vernal Field Office
MMS-Reference Data Branch, MS 3130, Box 5860, Denver, CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114-5801
Irene Anderson (UT-932)
Teresa Thompson (UT-931)
LaVerne Steah (UT-942)

Dominion Exploration & Production, Inc.
1450 Poydras Street, New Orleans, LA 70112-6000
Phone: 504-593-7000



June 27, 2000

Mr. Jimmy Thompson
Utah Board of Oil Gas & Mining
1594 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

RE: Name Change Documentation for CNG Producing Company

Dear Mr. Thompson:

CNG Producing Company has become Dominion Exploration & Production, Inc. effective April 12, 2000. Enclosed please find a sundry regarding the name change with an attached listing of all the permits in the name of CNG Producing Company to be changed to Dominion Exploration & Production, Inc. Also enclosed please find a Form UIC 5 for the Transfer of Authority to Inject for the Federal #1-26B well.

If you have any questions or require any additional information, please contact me at (504) 593-7260.

Sincerely,

DOMINION EXPLORATION & PRODUCTION, INC.

A handwritten signature in cursive script that reads "Susan H. Sachitana".

Susan H. Sachitana
Regulatory Reports Administrator

Enclosure

cc: Nelda Decker

RECEIVED

JUN 29 2000

**DIVISION OF
OIL, GAS AND MINING**

STATE OF UTAH
DIVISION OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well : OIL ☐ GAS ☐ OTHER:2. Name of Operator:
DOMINION EXPLORATION & PRODUCTION, INC.3. Address and Telephone Number:
1460 Poydras Street, New Orleans, LA 70112-6000 (504) 593-72604. Location of Well
Footages:
QQ, Sec, T., R., M.:5. Lease Designation and Serial Number:
VARIOUS

6. If Indian, Allottee or Tribe Name:

7. Unit Agreement Name:

8. Well Name and Number:
VARIOUS

9. API Well Number

10. Field and Pool, or Wildcat:
Natural Buttes 630County: UINTAH
State: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(SUBMIT IN DUPLICATE)

- ☐ Abandon ☐ New Construction
☐ Repair Casing ☐ Pull or Alter Casing
☐ Change of Plans ☐ Recomplete
☐ Convert to Injection ☐ Reperforate
☐ Fracture Treat or Acidize ☐ Vent or Flare
☐ Multiple Completion ☐ Water Shut-Off
☐ Other

Approximate date work will start

SUBSEQUENT REPORT
(Submit Original Form Only)

- ☐ Abandon* ☐ New Construction
☐ Repair Casing ☐ Pull or Alter Casing
☐ Change of Plans ☐ Reperforate
☐ Convert to Injection ☐ Vent or Flare
☐ Fracture Treat or Acidize ☐ Water Shut-Off
☒ Other OPERATOR NAME CHANGE FOR WELLS

Date of work completion

Report results of Multiple Completion and Recompletion to different reservoirs on WELL
COMPLETION OR RECOMPLETION REPORT AND LOG form.

*Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETION OPERATIONS (Clearly State all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that effective April 12, 2000, CNG Producing Company has changed its name to Dominion Exploration & Production, Inc. and would like to transfer the well permits into the name of Dominion Exploration & Production, Inc. Our new bond has been filed and is pending approval with the State of Utah. The bond number is 76S 63050 361.

John R. Lewis

Sr. Vice-President - CNG Producing Company

RECEIVED

JUN 29 2000

DIVISION OF
OIL, GAS AND MINING

13.

Name & Signature:

John R. Lewis

Title: Sr. Vice-President - Dominion Expl. & Prod., Inc.

Date: June 26, 2000

(This space for State use only)



State of Utah
DEPARTMENT OF COMMERCE
Division of Corporations & Commercial Code

**Application To Amend The
CERTIFICATE OF AUTHORITY OR
REGISTRATION of**

552894
CO 106990

File Number

Check Appropriate Box	
<input checked="" type="checkbox"/>	Foreign Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Non-Profit Corporation \$35.00
<input type="checkbox"/>	Foreign Limited Partnership \$25.00
<input type="checkbox"/>	Foreign Limited Liability Company \$35.00

CNG Producing Company
Business Entity Name

Delaware
Name of Home State

I. AMENDING THE BUSINESS NAME

The business name is changed to: Dominion Exploration & Production, Inc.

The corporation shall use as its name in Utah: Dominion Exploration & Production, Inc.

(The corporation shall use its name as set forth on #1, unless this name is not available)

NOTE: If the business name has changed its name in the home state, a copy of the Certificate of Amendment or a certified copy of the amendment must accompany this application.

Check the following:

- ☒ The name of the corporation is changing its name in Utah to the new name of the corporation in the home state.
☐ The name of the corporation is being changed in Utah to comply with Utah State Insurance Regulations.

II. AMENDING THE DURATION OF THE BUSINESS EXISTENCE

The businesses period of duration is changed to: _____

III. AMENDING THE STATE OR COUNTRY OF INCORPORATION/REGISTRATION

The corporation's state or country of incorporation/registration is changed to: _____

IV. Other: _____

(Limited Partnership changing General Partners, Limited Companies changing Members or Managers, Change of statement who is managing, etc.)
Use an attached sheet if needed.

Under penalties of perjury, I declare this Application to Amend the Certificate of Authority or Registration to be, to the best of my knowledge and belief, true and correct.

Signature

Vice President & Corporate Secretary
Title

April 20 2000

State of Utah
Department of Commerce

Division of Corporations and Commercial Code

I hereby certify that the foregoing has been filed and approved on this 25 day of April, 2000 in the office of this Division and hereby issue this Certificate thereof.

Examiner

Date



L. JENSEN
DIRECTOR

Date: 04/25/2000

Receipt Number: 22156

Amount Paid: \$50.00

STATE OF UTAH
DIVISION OF CORPORATIONS
AND COMMERCIAL CODE
160 East 300 South / Box 146705
Salt Lake City, UT 84114-6705
Service Center: (801) 530-4849

Web Site: <http://www.commerce.state.ut.us>

FILED

APR 25 2000

EXHIBIT A
OIL & GAS LEASES AFFECTED BY THE NAME CHANGE

U-01470-A	U-017713	U-46825
U-01790	U-035316	U-62232
U-02896-A	U-037164	UTU-66743
U-03505	U-0143519	UTU-68108
U-03576	U-0143520-A	UTU-68388
U-013429-A	U-0143521-A	UTU-68625
U-013765	U-0147541	UTU-69166
U-013766	U-0147541-A	UTU-73011
U-013767	U-3405	UTU-73433
U-013769	U-7206	UTU-76499
U-013769-A	U-9803	UTU-76500
U-013769-B	U-10291	UTU-76717
U-013769-C	U-16544	UTU-76718
U-013792	U-19266	
U-013793	U-28203	U-60759 (CA)
U-013793-A	U-29784	U-60940 (CA)
U-013794	U-30693	UTU-77360 (CA)
U-013818-A	U-37246	U-63054X (River Bend)
U-013820	U-39221	UTU-73218X
U-013821-A	U-43156	(West Willow Creek Unit)

Well Name	Api Well Code	Operator Name	Production Status	Lease Type
EVANS FEDERAL #32-25	4304732406	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-25B	4304732445	DOMINION EXPLORATION & PR	LA	BLM
RBU #5-25B	4304732453	DOMINION EXPLORATION & PR	LA	BLM
RBU #11-25B	4304732482	DOMINION EXPLORATION & PR	LA	BLM
RBU #16-14EO	4304732507	DOMINION EXPLORATION & PR	LA	BLM
RBU #8-23EO	4304732508	DOMINION EXPLORATION & PR	LA	BLM
RBU #8-14EO	4304732514	DOMINION EXPLORATION & PR	LA	BLM
RBU #15-13EO	4304732599	DOMINION EXPLORATION & PR	LA	BLM
RBU #9-23EO	4304732601	DOMINION EXPLORATION & PR	LA	BLM
STATE #2-36E	4304732979	DOMINION EXPLORATION & PR	PR	STATE
STATE #1-36E	4304732979	DOMINION EXPLORATION & PR	PR	STATE
RBU #1-16F	4304733181	DOMINION EXPLORATION & PR	PR	STATE
RBU #5-3F	4304733360	DOMINION EXPLORATION & PR	DR	STATE
RBU #5-16F	4304733361	DOMINION EXPLORATION & PR	FUT	BLM
RBU #10-23F	4304733363	DOMINION EXPLORATION & PR	PR	BLM
EVANS FEDERAL #15-26E	4304733367	DOMINION EXPLORATION & PR	DR	BLM
EVANS FEDERAL #9-26E	4304733508	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #10-25E	4304733509	DOMINION EXPLORATION & PR	FUT	BLM
EVANS FEDERAL #14-25E	4304733510	DOMINION EXPLORATION & PR	FUT	BLM
FEDERAL #13-30B	4304733511	DOMINION EXPLORATION & PR	FUT	BLM
STATE #13-36A	4304733581	DOMINION EXPLORATION & PR	FUT	BLM
RBU #1-1D	4304733598	DOMINION EXPLORATION & PR	FUT	STATE
OSC #1-17 *	4304733599	DOMINION EXPLORATION & PR	FUT	BLM
OSC #2 *	430472030800S1	DOMINION EXPLORATION & PR	SIEC	BLM
OSC #4 *	430473008700S1	DOMINION EXPLORATION & PR	PR	BLM
OSC #4A-30 *	430473011300S1	DOMINION EXPLORATION & PR	TA	BLM
OSC #7-15E *	430473012200S1	DOMINION EXPLORATION & PR	SIEC	BLM
RBU #11-16E	430473021100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-18F	430473026000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #11-13E	430473026600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-15F	430473037400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-21F	430473037500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-19F	430473037600S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL #7-25B	430473040500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-10E	430473040600S01	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-11D	430473040800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-14E	430473040900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-23E	430473041000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-16F	430473041100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-17F	430473041200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-11F	430473058400S1	DOMINION EXPLORATION & PR	PA	BLM
RBU #8-16D	430473058500S1	DOMINION EXPLORATION & PR	PR - RBU	BLM
FEDERAL #7-25A	4304730608	DOMINION EXPLORATION & PR	PA	STATE
RBU #11-3F	430473062400S01	DOMINION EXPLORATION & PR	PA	BLM
RBU #11-22E	430473068900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #4-11D	430473069800S1	DOMINION EXPLORATION & PR	PA	BLM
RBU #16-23F	430473071800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-3E	4304730719	DOMINION EXPLORATION & PR	PA	BLM
RBU #11-24E	430473072000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-2F	430473075900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-10F	430473076000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #6-20F	430473076100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-22F	430473076200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-14F	430473076800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #2-11D	430473076800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-3F	430473082500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-15E	430473082600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-14E	430473088700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-22E	430473091500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-23E	430473092600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #4-19F	430473092700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-11F	430473097000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-10E	430473097100S1	DOMINION EXPLORATION & PR	PR	BLM
	430473097300S1	DOMINION EXPLORATION & PR	PR	BLM
	430473104600S1	DOMINION EXPLORATION & PR	PR	BLM

Well Name	Api Well Code	Operator Name	Production Status	Lease Type
RBU #16-16F	430473111500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-34B	430473113800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #12-18F	430473114000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-24E	430473114100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-23E	430473114300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-23E	430473114400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-14E	430473114500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-15E	430473116000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-15E	430473116100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-10E	430473117600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #14-2D	430473119100S1	DOMINION EXPLORATION & PR	SIEC	STATE
RBU #6-11D	430473119200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-14E	430473119600S1	DOMINION EXPLORATION & PR	PR	BLM
FEDERAL 33-18J	430473120000S01	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-4E	430473125200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-2D	430473128000S1	DOMINION EXPLORATION & PR	PR	STATE
RBU #1-19F	430473132200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-10E	430473132300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-20F	430473132400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-3D	430473135200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-11D	430473135700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-11D	430473135800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-10D	430473136400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-13E	430473136900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #12-2D	4304731452S02	DOMINION EXPLORATION & PR	PR	STATE
RBU #16-3E	430473151800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-11F	430473151900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-17F	430473152000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-3D	430473153900S1	DOMINION EXPLORATION & PR	PR	BLM
* HILL CREEK FEDERAL #1-30	430473160100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-13E	430473160500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #3-22E	430473160600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-24E	430473160700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-18F	430473160800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-11F	430473161300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #8-16F	430473161400S2	DOMINION EXPLORATION & PR	PR	BLM
RBU #4-22F	430473161500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #12-12D	430473165100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #6-17E	430473165200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-13E	430473171500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-13E	430473171700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-35B	430473172400S1	DOMINION EXPLORATION & PR	TA	BLM
RBU #9-9E	430473173900S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #1-16E	430473174000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #2-10D	430473180100S1	DOMINION EXPLORATION & PR	PR - RBU	BLM
APACHE FEDERAL #12-25	430473188100S1	DOMINION EXPLORATION & PR	PR	BLM BIA
APACHE FEDERAL #44-25	430473192200S2	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-2F	430473202600S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-14E	430473203300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-3E	430473203700S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #6-18F	430473203800S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-24E	430473204000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #5-14E	430473204100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-16E	430473204200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #12-20F	430473205000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #7-13E	430473205100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #16-19F	430473207000S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-22E	430473207100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-34B	430473207200S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #11-15E	430473207300S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #13-21F	430473207400S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #10-22F	430473207500S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #9-20F	430473208100S1	DOMINION EXPLORATION & PR	PR	BLM
RBU #15-23E	430473208200S1	DOMINION EXPLORATION & PR	PR	BLM

Result - select api, well_name, w

api	well_name	well_status_main	lease_num
4304732111	RBU 7-15F	LA	14-20-H62-2645
4304732189	RBU 13-10F	P	14-20-H62-2645
4304730768	RBU 7-22F	P	14-20-H62-2646
4304732109	RBU 15-15F	LA	14-20-H62-2646
4304732844	RBU 15-15F	P	14-20-H62-2646
4304732269	RBU 4-15F	PA	INDIAN
4304733360	RBU 1-16F	DRL	ML-3393
4304731980	STATE 2-36E	LA	ML-42175
4304731801	RIVER BEND U 2-10D	S	U-013429-A
4304731551	RBU 10X-15E	PA	U-013760
4304731716	RIVER BEND U 7-13E	LA	U-013765
4304731718	RBU 15-13E	LA	U-013765
4304732600	RBU 1-21EO	P	U-013766
4304733033	RBU 7-23E	P	U-013766
4304733160	RBU 8-15E	P	U-013766
4304733272	RBU 13-3F	P	U-013767
4304733366	RBU 5-18F	P	U-013769
4304732991	RBU 6-19F	P	U-013769-A
4304733157	RBU 7-19F	P	U-013769-A
4304732454	RBU 9-14EO	P	U-013792
4304732514	RBU 8-14EO	LA	U-013792
4304732678	RBU 13-22EO	LA	U-013792
4304732989	RBU 13-10E	P	U-013792
4304733156	RBU 4-14E	P	U-013792
4304733161	RBU 16-10E	P	U-013792
4304733194	RBU 2-14E	P	U-013792
4304733365	RBU 12-14E	P	U-013792
4304732990	RBU 13-18F2	P	U-013793
4304732396	RBU 3-21F	P	U-013793-A
4304732407	RBU 15-14F	P	U-013793-A
4304732408	RBU 4-23F	P	U-013793-A
4304732899	RBU 3-14F	P	U-013793-A
4304732900	RBU 8-23F	P	U-013793-A
4304732972	RBU 1-21F	P	U-013793-A
4304733087	RBU 6-23F	P	U-013793-A
4304733158	RBU 7-20F	P	U-013793-A
4304733424	RBU 5-20F	P	U-013793-A
4304732392	RBU 11-14F	P	U-013793A
4304731719	RBU 5-24E	LA	U-013794
4304732483	RBU 5-24EO	P	U-013794
4304733034	RBU 9-18F	P	U-013794
4304733159	RBU 7-24E	P	U-013794
4304731352	RBU 16-3D	P	U-013820
4304733599	RBU 1-1D	APD	U-013820
4304733090	RBU 11-22F	P	U-0143519
4304733089	RBU 8-22F	P	U-0143521
4304732901	RBU 12-23F	P	U-01470-A
4304733091	RBU 16-22F	P	U-01470-A
4304733368	RBU 14-23F	P	U-01470-A
4304731138	RBU 11-34B	P	U-017713
4304731724	RBU 11-35B	S	U-017713
4304732094	RBU 13-35B	P	U-017713
4304732222	RBU 15-35B	S	U-017713
4304730585	RBU 7-11F	P	U-01790
4304732512	RBU 8-11F	P	U-01790
4304731739	RBU 9-9E	P	U-03505
4304732415	RBU 3-10EX (RIG SKID)	P	U-035316
4304733035	RBU 14-19F	P	U-13769-A
4304731881	APACHE 12-25	S	U-3405
4304732417	FEDERAL 3-25B	P	U-39221
4304731782	SADDLE TREE DRAW 13-34	LA	U-57598
4304732934	RBU 3-10F	P	U-7206
4304732969	RBU 11-10F	P	U-7206
4304732970	RBU 12-15F	P	U-7206
4304732971	RBU 15-16F	P	U-7206

OPERATOR CHANGE WORKSHEET

Check each listed item when completed. Write N/A if item is not applicable.

ROUTING:

1-KAS	4-KAS ✓
2-CDWL ✓	5-SP ✓
3-JLT	6-FILE

Change of Operator (Well Sold)

Designation of Agent

X Operator Name Change Only

Merger

The operator of the well(s) listed below has changed, effective: 4-12-00TO:(New Operator) DOMINION EXPL & PROD INC.Address: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Phone: 1-(504)-593-7000Account No. N1095FROM:(Old Operator) CNG PRODUCING COMPANYAddress: 1450 POYDRAS STREET
NEW ORLEANS, LA 70112-6000Phone: 1-(504)-593-7000Account No. N0605

WELL(S):	CA Nos.	or	RIVER BEND	Unit
Name: RBU 7-11F	API: 43-047-30585	Entity: 7050	S 11 T 10S R 20E	Lease: U-01790
Name: RBU 2-10D	API: 43-047-31801	Entity: 10784	S 10 T 10S R 18E	Lease: U-013249-A
Name: RBU 1-16F	API: 43-047-33360	Entity: 7050	S 16 T 10S R 20E	Lease: ML-3393
Name: RBU 8-15E	API: 43-047-33160	Entity: 7050	S 15 T 10S R 19E	Lease: U-013766
Name: RBU 13-3F	API: 43-047-33272	Entity: 7050	S 03 T 10S R 20E	Lease: U-013767
Name: RBU 5-18F	API: 43-047-33366	Entity: 7050	S 18 T 10S R 20E	Lease: U-013769
Name: RBU 6-19F	API: 43-047-32991	Entity: 7050	S 19 T 10S R 20E	Lease: U-013769-A
Name: RBU 7-19F	API: 43-047-33157	Entity: 7050	S 19 T 10S R 20E	Lease: U-013769-A
Name: RBU 9-14EO	API: 43-047-32454	Entity: 11718	S 14 T 10S R 19E	Lease: U-013792
Name: RBU 13-10E	API: 43-047-32989	Entity: 7050	S 10 T 10S R 19E	Lease: U-013792
Name: RBU 4-14E	API: 43-047-33156	Entity: 7050	S 14 T 10S R 19E	Lease: U-013792
Name: RBU 16-10E	API: 43-047-33161	Entity: 7050	S 10 T 10S R 19E	Lease: U-013792
Name: RBU 2-14E	API: 43-047-33194	Entity: 7050	S 14 T 10S R 19E	Lease: U-013792
Name: RBU 12-14E	API: 43-047-33365	Entity: 7050	S 14 T 10S R 19E	Lease: U-013792
Name: RBU 13-18F2	API: 43-047-32990	Entity: 7050	S 18 T 10S R 20E	Lease: U-013793
Name: RBU 3-21F	API: 43-047-32396	Entity: 7050	S 21 T 10S R 20E	Lease: U-013793-A
Name: RBU 15-14F	API: 43-047-32407	Entity: 7050	S 14 T 10S R 20E	Lease: U-013793-A
Name: RBU 4-23F	API: 43-047-32408	Entity: 7050	S 23 T 10S R 20E	Lease: U-013793-A
Name: RBU 3-14F	API: 43-047-32899	Entity: 7050	S 14 T 10S R 20E	Lease: U-013793-A
Name: RBU 8-23F	API: 43-047-32900	Entity: 7050	S 23 T 10S R 20E	Lease: U-013793-A

OPERATOR CHANGE DOCUMENTATION

YES 1. A pending operator change file has been set up.YES 2. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator on 6-29-00.YES 3. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 6-29-00.YES 4. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? **Yes/No** If yes, the company file number is SEE ATTACHED. If no, Division letter was mailed to the new operator on _____.

- YES 5. **Federal and Indian Lease Wells.** The BLM or the BIA has approved the merger, name change or operator change for all wells listed above involving Federal or Indian leases on 6-2-00.
- N/A 6. **Federal and Indian Units.** The BLM or the BIA has approved the successor of unit operator for all wells listed above involving unit operations on _____.
- N/A 7. **Federal and Indian Communitization Agreements ("CA").** The BLM or the BIA has approved the operator change for all wells listed above involved in the CA on _____.
- N/A 8. **Underground Injection Control ("UIC") Program.** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project and/or for the water disposal well(s) listed above.
- YES 9. Changes have been entered in the **Oil and Gas Information System** for each well listed on 8-1-00.
- YES 10. Changes have been included on the **Monthly Operator Change letter** on 8-1-00.

STATE BOND VERIFICATION

- N/A 1. State Well(s) covered by Bond No. 76S63050361.

FEE WELLS - BOND VERIFICATION / LEASE INTEREST OWNER NOTIFICATION

- N/A 1. (R649-3-1) The **NEW** operator of any fee lease well(s) listed above has furnished a proper bond.
- N/A 2. A copy of this form has been placed in the **new and former operator's bond files** on _____.
- N/A 3. The **FORMER** operator has requested a release of liability from their bond as of today's date _____? If yes, Division response was made to this request by letter dated _____. (see bond file).
- N/A 4. (R649-2-10) The **Former** operator of any Fee lease wells listed above has been contacted and informed by letter dated _____, of their responsibility to notify all interest owners of this change.
- N/A 5. Bond information added to **RBDMS** on _____.
- N/A 6. Fee wells attached to bond in **RBDMS** on _____.

FILMING

- ____ 1. All attachments to this form have been **microfilmed** on 2-22-01.

FILING

- ____ 1. **Originals/Copies** of all attachments pertaining to each individual well have been filed in each **well file**.
- ____ 2. The **original of this form** has been filed in the operator file and a copy in the old operator file.

COMMENTS

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING	
1. DJJ	
2. CDW	

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

7/1/2006

FROM: (Old Operator):

N1095-Dominion E&P, Inc.

14000 Quail Springs Pkwy, Suite 600

Oklahoma City, OK 73134

Phone: 1 (405) 749-1300

TO: (New Operator):

N2575-Gasco Production Company

8 Inverness Dr E, Suite 100

Englewood, CO 80112

Phone: 1 (303) 483-0044

CA No.

Unit:

WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
RBU 2-11D	11	100S	180E	4304730826	7070	Federal	OW	S
SQUAW CROSSING U 5	02	100S	180E	4304730129	7070	State	OW	P
RBU 5-11D	11	100S	180E	4304730409	9005	Federal	GW	P
RBU 4-11D	11	100S	180E	4304730718	7070	Federal	OW	S
RBU 6-2D	02	100S	180E	4304731190	7075	State	OW	S
RBU 14-2D	02	100S	180E	4304731191	7070	State	OW	PA
RBU 6-11D	11	100S	180E	4304731192	7070	Federal	OW	P
RBU 13-2D	02	100S	180E	4304731280	7070	State	OW	P
RBU 16-3D	03	100S	180E	4304731352	7070	Federal	OW	P
RBU 16-2D	02	100S	180E	4304731353	7091	State	OW	PA
RBU 10-11D	11	100S	180E	4304731357	7053	Federal	OW	S
RBU 8-11D	11	100S	180E	4304731358	7054	Federal	OW	S
RBU 8-10D	10	100S	180E	4304731364	4955	Federal	OW	P
RBU 12-2D	02	100S	180E	4304731452	9041	State	OW	PA
RBU 15-3D	03	100S	180E	4304731539	9965	Federal	OW	S
RBU 12-12D	12	100S	180E	4304731651	10688	Federal	GW	P
RBU 2-10D	10	100S	180E	4304731801	10784	Federal	OW	P
RBU 3-10D	10	100S	180E	4304731832	4955	Federal	NA	PA
RBU 1-10D	10	100S	180E	4304734312	14493	Federal	GW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/24/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/24/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 5/17/2004
- Is the new operator registered in the State of Utah: YES Business Number: 1454161-0143
- If **NO**, the operator was contacted on: _____
- (R649-9-2) Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a
- Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 8/30/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 8/30/2006
- Bond information entered in RBDMS on: 8/30/2006
- Fee/State wells attached to bond in RBDMS on: 8/30/2006

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UT1233 State/Fee Wells 4127763

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
Dominion Exploration & Production, Inc. N1095

3. ADDRESS OF OPERATOR: 14000 Quail Springs CITY Oklahoma City STATE OK ZIP 73134 PHONE NUMBER: (405) 749-1300

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
See Attached List

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective July 1, 2006, Dominion Exploration & Production, Inc. has sold the wells on the attached list to:

Gasco Production Company N 2575
8 Inverness Drive East, Suite 100
Englewood, CO 80112

John D. Longwell - V.P. Operations
(303) 483-0044

UT1233 - State Wide BLM Bond
4127763 - Blanket Drilling Bond

RECEIVED
AUG 24 2006

DIV OF OIL, GAS & MINING

NAME (PLEASE PRINT) Jason Garner TITLE Asset Manager - Rocky Mountain Division
SIGNATURE J.A. Garner DATE 8/10/2006

(This space for State use only)

APPROVED 8/30/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(5/2000)

(See Instructions on Reverse Side)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. U-013429-A
2. Name of Operator Gasco Production Company		6. If Indian, Allottee, or Tribe Name
3a. Address 8 Inverness Drive East Ste 100 Englewood, Co 80112	3b. Phone No. (include area code) 303-483-0044	7. If Unit or CA, Agreement Name and/or No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)		8. Well Name and No. See list below
		9. API Well No.
		10. Field and Pool, or Exploratory Area
		11. County or Parish, State

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Altering Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

This is to inform you that effective immediately we will be disposing of produced water from wells within this lease as follows:

All produced water from this well will be trucked off the location and disposed of at the Desert Spring State Evaporation Facility NW 1/4 of Section 36-T9S-R18E Uintah County, Utah. Which is owned by Gasco Production Company. A copy of the approved permit for this facility is attached.

The wells within this lease are:

RBu 1-10D NE NE of Sec 10-T10S-R18E Uintah Cnty, Utah 043-047-34312
**RBu 2-10D NW NE of Sec 10-T10S-R18E Uintah Cnty, Utah 043-047-31801*
RBu 3-15D NE NW of Sec 15-T10S-R18E Uintah Cnty, Utah 043-047-33600
RBu 8-10D SE NE of Sec 10-T10S-R18E Uintah Cnty, Utah 043-047-31364
RBu 8-10D SE NE of Sec 11-T10S-R18E Uintah Cnty, Utah 043-047-31358
RBu10-11D NW SE of Sec 11-T10S-R18E Uintah Cnty, Utah 043-047-31357

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
RECEIVED

OCT 24 2006

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct.	
Name (Printed Typed) Beverly Walker	Title Engineering Tech
Signature <i>Beverly Walker</i>	Date October 18, 2006

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of approval, if any are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001 AND Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.	<i>U-013429-A</i>
6. If Indian, Allottee or Tribe Name	<i>NA</i>
7. If Unit or CA/Agreement, Name and/or No.	
8. Well Name and No.	<i>RBU 2-10D</i>
9. API Well No.	<i>43-047-31801</i>
10. Field and Pool, or Exploratory Area	<i>Uteland Butte</i>
11. County or Parish, State	<i>Uintah County, Utah</i>

SUBMIT IN TRIPLICATE – Other instructions on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other	
2. Name of Operator <i>Gasco Production Company</i>	
3a. Address <i>8 Inverness Dr E, Englewood, Colorado 80112</i>	3b. Phone No. (include area code) <i>303-483-0044</i>
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) <i>734' FNL & 2013' FEL NW NE of Section 10-T10S-R18E</i>	

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	<i>Site Security</i>
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Please find attached a copy of the site security diagram for this well.

14. I hereby certify that the foregoing is true and correct	
Name (Printed/Typed) <i>Beverly Walker</i>	Title <i>Engineering Technician</i>
Signature <i>[Signature]</i>	Date <i>March 8, 2007</i>





THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

RECEIVED
MAR 12 2007
DIV. OF OIL, GAS & MINING



This lease is subject to the Site Security Plan for GASCO Production Company. The Plan is located at: GASCO Production Company, 8 Inverness Drive East, Suite 100, Englewood, CO 80112-5625.

LEGEND	
S	Sales Valve
D	Drain Valve
I	Inlet Valve
O	Overflow
B	Blowdown
V	Vent

POSITION OF VALVES AND USE OF SEALS DURING PRODUCTION/BLOWDOWN

Valves	Line Purpose	Position	Seal Installed
D	Drain	Closed	Yes
S	Sales	Closed	Yes
I	Inlet	Open	No
O	Overflow	Open/Closed	No
B	Blowdown	Open/Closed	No

POSITION OF VALVES AND USE OF SEALS DURING SALES

Valves	Line Purpose	Position	Seal Installed
D	Drain	Closed	Yes
S	Sales	Open	No
I	Inlet	Closed	Yes
O	Overflow	Closed	Yes
B	Blowdown	Closed	Yes

POSITION OF VALVES AND USE OF SEALS DURING WATER DRAIN

Valves	Line Purpose	Position	Seal Installed
D	Drain	Open	No
S	Sales	Closed	Yes
I	Inlet	Closed	No
O	Overflow	Closed	No
B	Blowdown	Closed	No

2-55g Dexron

BUYS & ASSOCIATES, INC. ENVIRONMENTAL CONSULTANTS

GASCO Production Company
RBU 2-10D
NW/NE Sec. 10, Twp. 10S, Rge. 18E
Uintah County, Utah

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-013429-A			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: RIVER BEND			
2. NAME OF OPERATOR: GASCO PRODUCTION COMPANY		8. WELL NAME and NUMBER: RBW 2-10D			
3. ADDRESS OF OPERATOR: 8 Inverness Dr. East, Suite 100, Englewood, CO, 80112		9. API NUMBER: 43047318010000			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0734 FNL 2013 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 10 Township: 10.0S Range: 18.0E Meridian: S		9. FIELD and POOL or WILDCAT: UTELAND BUTTE			
COUNTY: UINTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 2/15/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Gasco intends to re-contour and reclaim a portion of the 2-10D pad location based on discussions with our BLM Natural Resource Specialist.					
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 17, 2012					
NAME (PLEASE PRINT) Roger Knight		PHONE NUMBER 303 996-1803			
SIGNATURE N/A		TITLE EHS Supervisor			
DATE 2/8/2012					

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-013420-A			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR:		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: , , , Ext		8. WELL NAME and NUMBER: RBU 2-10D			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0734 FNL 2013 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 10 Township: 10.0S Range: 18.0E Meridian: S		9. API NUMBER: 43047318010000			
9. FIELD and POOL or WILDCAT: UTELAND BUTTE		9. COUNTY: UINTAH			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/10/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input checked="" type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Adding surface equipment </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input checked="" type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Adding surface equipment
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input checked="" type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Adding surface equipment			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Gasco intends to change the status of the RBU 2-10D to producing from shut in. This will include raising the tubing and adding a 400 bbl tank and an Ajax engine for the exisiting pumping unit to the location.					
		Accepted by the Utah Division of Oil, Gas and Mining Date: July 12, 2012 By:			
NAME (PLEASE PRINT) Jessica Berg		PHONE NUMBER 303 996-1805			
SIGNATURE N/A		TITLE Production Tech			
		DATE 7/3/2012			

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-013420-A
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR:		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: , , , Ext		8. WELL NAME and NUMBER: RBU 2-10D
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0734 FNL 2013 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 10 Township: 10.0S Range: 18.0E Meridian: S		9. API NUMBER: 43047318010000
9. FIELD and POOL or WILDCAT: UTELAND BUTTE		COUNTY: UINTAH
STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/19/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input checked="" type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Gasco intends to set an additional 400 bbl tank on this location.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY November 08, 2012		
NAME (PLEASE PRINT) Lindsey J. Cooke		PHONE NUMBER 303 996-1834
SIGNATURE N/A		TITLE Production Tech
DATE 11/6/2012		

Rm
BSH
PIC



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
440 West 200 South, Suite 500
Salt Lake City, UT 84101
<http://www.blm.gov/ut/st/en.html>



RECEIVED

JUN 02 2014

IN REPLY REFER TO:
3180 (UTU90215X)
UT9220000

MAY 29 2014

DIV. OF OIL, GAS & MINING

Mr. Brandon Casey
Gasco Energy, Inc. N2575
7979 East Tufts Avenue, Suite 1150
Denver, Colorado 80237
unit # 830
Dear Mr. Casey:

Your application of May 8, 2014, filed with the Bureau of Land Management, Branch of Minerals, Salt Lake City, Utah, requests the designation of the River Bend Green River Enhanced Recovery Unit, embracing 2,480.68 acres located in Uintah County, Utah, as logically subject to operations under unitization provisions of the Mineral Leasing Act, as amended, and acceptance of the proposed form of unit agreement.

Pursuant to unit plan regulations 43 CFR 3105, the land requested as outlined on your plat marked "Exhibit 'A' River Bend Green River Enhanced Recovery", Contract No. UTU90215X, is acceptable as a logical unit area for the purpose of enhanced recovery operations.

The form of unit agreement and Exhibits "A", "B" and "C" as submitted with your application are acceptable. In the absence of any objections not now apparent, a duly executed agreement, identical with said form, will be approved if submitted in approvable status within a reasonable period of time.

If you have any questions, please contact Judy Nordstrom of this office at (801) 539-4080.

Sincerely,

Roger L. Bankert
Chief, Branch of Minerals

cc: UDOGM
SITLA
BLM FOM – Vernal (UTG01) w/enclosures

River Bend Green River Enhanced Recover Unit
Effective 1 September 2014

Well Name	Section	TWN	RNG	API Number	Type	Status
RBU 6-2D	2	100S	180E	4304731190	OW	P
RBU 13-2D	2	100S	180E	4304731280	OW	P
UTELAND ST 41-2-10-18	2	100S	180E	4304737132	GW	P
UTELAND ST 43-2-10-18	2	100S	180E	4304737338	GW	P
UTELAND ST 21-2-10-18	2	100S	180E	4304737676	GW	P
UTELAND ST 12-2-10-18	2	100S	180E	4304737677	GW	P
UTELAND ST 34-2-10-18	2	100S	180E	4304738028	GW	P
SQUAW CROSSING U 5	2	100S	180E	4304730129	OW	S
RBU 16-3D	3	100S	180E	4304731352	OW	P
RBU 15-3D	3	100S	180E	4304731539	OW	P
RBU 8-10D	10	100S	180E	4304731364	OW	P
RBU 2-10D	10	100S	180E	4304731801	OW	P
RBU 1-10D	10	100S	180E	4304734312	OW	S
RBU 5-11D	11	100S	180E	4304730409	OW	P
RBU 10-11D	11	100S	180E	4304731357	OW	P
UTELAND FED 42-11-10-18	11	100S	180E	4304738896	GW	P
RBU 4-11D	11	100S	180E	4304730718	OW	S
RBU 2-11D	11	100S	180E	4304730826	OW	S
RBU 6-11D	11	100S	180E	4304731192	OW	S
RBU 12-12D	12	100S	180E	4304731651	OW	P
RBU 3-12D	12	100S	180E	4304733739	OW	P

Effective Date: 4/16/2015

FORMER OPERATOR:	NEW OPERATOR:
Gasco Production Company N2575 7979 E. Tufts Avenue, Suite 11500 Denver, CO 80237 303-996-1805	Badlands Production Company N4265 7979 E. Tufts Avenue, Suite 11500 Denver, CO 80237 303-996-1805
CA Number(s):	Unit(s): Gate Canyon, Wilkin Ridge Deep, RBU-EOR-GRRV

WELL INFORMATION:

Well Name	Sec	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
See Attached List									

OPERATOR CHANGES DOCUMENTATION:

1. Sundry or legal documentation was received from the **FORMER** operator on: 6/2/2015
2. Sundry or legal documentation was received from the **NEW** operator on: 6/2/2015
3. New operator Division of Corporations Business Number: 1454161-0143

REVIEW:

1. Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: 6/2/2015
2. Receipt of Acceptance of Drilling Procedures for APD on: N/A
3. Reports current for Production/Disposition & Sundries: 6/3/2015
4. OPS/SI/TA well(s) reviewed for full cost bonding: 1/20/2016
5. UIC5 on all disposal/injection/storage well(s) approved on: N/A
6. Surface Facility(s) included in operator change: None
7. Inspections of PA state/fee well sites complete on (only upon operators request): N/A

NEW OPERATOR BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: SUR0027842
2. Indian well(s) covered by Bond Number: N/A
3. State/fee well(s) covered by Bond Number(s): SUR0027845
SUR0035619 -FCB

DATA ENTRY:

1. Well(s) update in the **OGIS** on: 1/22/2016
2. Entity Number(s) updated in **OGIS** on: 1/22/2016
3. Unit(s) operator number update in **OGIS** on: 1/22/2016
4. Surface Facilities update in **OGIS** on: N/A
5. State/Fee well(s) attached to bond(s) in **RBDMS** on: 1/22/2016
6. Surface Facilities update in **RBDMS** on: N/A

LEASE INTEREST OWNER NOTIFICATION:

1. The **NEW** operator of the Fee (Mineral) wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 1/22/2016

COMMENTS:

From: Gasco Production Company
To: Badlands Production Company
Effective Date: 4/16/2015

Well Name	Section	TWN	RNG	API Number	Entity	Mineral	Surface	Type	Status
FEDERAL 23-18G-9-19	18	090S	190E	4304752496		Federal	Federal	OW	APD
FEDERAL 14-17G-9-19	17	090S	190E	4304752522		Federal	Federal	OW	APD
FEDERAL 13-18G-9-19	18	090S	190E	4304752538		Federal	Federal	OW	APD
FEDERAL 23-29G-9-19	29	090S	190E	4304752544		Federal	Federal	OW	APD
FEDERAL 24-20G-9-19	20	090S	190E	4304752545		Federal	Federal	OW	APD
FEDERAL 31-21G-9-19	21	090S	190E	4304752546		Federal	Federal	OW	APD
Federal 323-29-9-19	29	090S	190E	4304753026		Federal	Federal	GW	APD
Federal 421-29-9-19	29	090S	190E	4304753027		Federal	Federal	GW	APD
Federal 322-29-9-19	29	090S	190E	4304753029		Federal	Federal	GW	APD
Federal 431-29-9-19	29	090S	190E	4304753030		Federal	Federal	GW	APD
Federal 432-29-9-19	29	090S	190E	4304753031		Federal	Federal	GW	APD
Federal 414-29-9-19	29	090S	190E	4304753070		Federal	Federal	GW	APD
FEDERAL 412-29-9-19	29	090S	190E	4304753073		Federal	Federal	GW	APD
FEDERAL 213-29-9-19	29	090S	190E	4304753076		Federal	Federal	GW	APD
federal 321-29-9-19	29	090S	190E	4304753078		Federal	Federal	GW	APD
FEDERAL 213-29-9-19	29	090S	190E	4304753079		Federal	Federal	GW	APD
FEDERAL 321-29-9-19	29	090S	190E	4304753080		Federal	Federal	GW	APD
Federal 212-29-9-19	29	090S	190E	4304753133		Federal	Federal	GW	APD
State 321-32-9-19	32	090S	190E	4304754479		State	State	GW	APD
State 423-32-9-19	32	090S	190E	4304754480		State	State	GW	APD
State 421-32-9-19	32	090S	190E	4304754481		State	State	GW	APD
State 413-32-9-19	32	090S	190E	4304754482		State	State	GW	APD
State 323-32-9-19	32	090S	190E	4304754483		State	State	GW	APD
State 431-32-9-19	32	090S	190E	4304754529		State	State	GW	APD
Desert Spring State 224-36-9-18	36	090S	180E	4304754541		State	State	GW	APD
Desert Spring State 243-36-9-18	36	090S	180E	4304754542		State	State	GW	APD
Desert Spring State 241-36-9-18	36	090S	180E	4304754543		State	State	GW	APD
FEDERAL 332-30-9-19	30	090S	190E	4304753012	19650	Federal	Federal	GW	DRL
WILKIN RIDGE FED 43-29-10-17	29	100S	170E	4301333098	15941	Federal	Federal	GW	OPS
LAMB TRUST 11-23-9-19	23	090S	190E	4304736915	16556	Fee	Fee	GW	OPS
SHEEP WASH FED 43-26-9-18	26	090S	180E	4304738573	17201	Federal	Federal	GW	OPS
FEDERAL 13-19-9-19	19	090S	190E	4304739777	18344	Federal	Federal	GW	OPS
FEDERAL 12-17-9-19	17	090S	190E	4304739800	17202	Federal	Federal	GW	OPS
GATE CYN 31-21-11-15	21	110S	150E	4301332391	13787	State	State	GW	P
WILKIN RIDGE ST 12-32-10-17	32	100S	170E	4301332447	14033	State	State	GW	P
GATE CYN 41-20-11-15	20	110S	150E	4301332475	14417	State	State	GW	P
WILKIN RIDGE FED 34-17-10-17	17	100S	170E	4301332560	14726	Federal	Federal	GW	P
GATE CYN 41-19-11-16	19	110S	160E	4301332611	14439	Federal	Federal	GW	P
WILKIN RIDGE ST 44-32-10-17	32	100S	170E	4301332619	15649	State	State	GW	P
WILKIN RIDGE FED 12-4-11-17	4	110S	170E	4301332674	15537	Federal	Federal	GW	P
WILKIN RIDGE ST 24-32-10-17	32	100S	170E	4301332676	15242	State	State	GW	P
WILKIN RIDGE FED 23-29-10-17	29	100S	170E	4301332679	14033	Federal	Federal	GW	P
GATE CYN ST 23-16-11-15	16	110S	150E	4301332685	16082	State	State	GW	P
WILKIN RIDGE ST 34-16-10-17	16	100S	170E	4301332730	15243	State	State	GW	P
WILKIN RIDGE FED 31-29-10-17	29	100S	170E	4301332773	15370	Federal	Federal	GW	P
WILKIN RIDGE 32-08	8	110S	170E	4301332778	14802	Federal	Federal	GW	P
GATE CYN ST 23-16-11-16	16	110S	160E	4301332888	15098	State	State	GW	P
WILKIN RIDGE FED 24-20-10-17	20	100S	170E	4301333081	15714	Federal	Federal	GW	P
WILKIN RIDGE FED 32-20-10-17	20	100S	170E	4301333087	15807	Federal	Federal	GW	P
WILKIN RIDGE FED 14-4-11-17	4	110S	170E	4301333099	15920	Federal	Federal	GW	P
RYE PATCH FED 22-21	22	110S	140E	4301333437	16919	Federal	Federal	GW	P
RYE PATCH FED 24-21	24	110S	140E	4301333443	16367	Federal	Federal	GW	P
SQUAW CROSSING U 5	2	100S	180E	4304730129	16266	State	State	OW	P
RBV 5-11D	11	100S	180E	4304730409	9005	Federal	Federal	OW	P
FEDERAL 7-25A	25	090S	180E	4304730624	9030	Federal	Federal	OW	P

From: Gasco Production Company
To: Badlands Production Company
Effective Date: 4/16/2015

RBU 6-2D	2	100S	180E	4304731190	7075	State	State	OW	P
NGC 33-18J	18	090S	190E	4304731200	6155	Federal	Federal	OW	P
RBU 13-2D	2	100S	180E	4304731280	16267	State	State	OW	P
RBU 16-3D	3	100S	180E	4304731352	16268	Federal	Federal	OW	P
RBU 10-11D	11	100S	180E	4304731357	7053	Federal	Federal	OW	P
RBU 8-10D	10	100S	180E	4304731364	4955	Federal	Federal	OW	P
RBU 15-3D	3	100S	180E	4304731539	9965	Federal	Federal	OW	P
RBU 12-12D	12	100S	180E	4304731651	10688	Federal	Federal	OW	P
RBU 2-10D	10	100S	180E	4304731801	10784	Federal	Federal	OW	P
RBU 3-15D	15	100S	180E	4304733600	13213	Federal	Federal	OW	P
RBU 3-12D	12	100S	180E	4304733739	14492	Federal	Federal	OW	P
STATE 7-36A	36	090S	180E	4304733741	14244	State	State	GW	P
FEDERAL 34-29	29	090S	190E	4304733750	13174	Federal	Federal	GW	P
FEDERAL 24-7 #1	7	100S	180E	4304733983	13182	Federal	Federal	GW	P
FEDERAL 23-29 #1	29	090S	190E	4304734111	13441	Federal	Federal	GW	P
FED 24-20-9-19	20	090S	190E	4304734168	14150	Federal	Federal	GW	P
FED 44-20-9-19	20	090S	190E	4304734169	14140	Federal	Federal	GW	P
FED 23-21-9-19	21	090S	190E	4304734199	13601	Federal	Federal	GW	P
FED 32-31-9-19	31	090S	190E	4304734201	13641	Federal	Federal	GW	P
FED 42-29-9-19	29	090S	190E	4304734202	13455	Federal	Federal	GW	P
PETES WASH 23-12 #1	12	100S	170E	4304734286	13492	Federal	Federal	GW	P
STATE 4-32B	32	090S	190E	4304734314	14440	State	State	GW	P
FED 14-18-2 #1	18	100S	180E	4304734539	13491	Federal	Federal	GW	P
FED 43-24-3 #1	24	100S	170E	4304734551	13726	Federal	Federal	GW	P
LYTHAM FED 22-22-9-19	22	090S	190E	4304734607	13640	Federal	Federal	GW	P
FED 11-21-9-19	21	090S	190E	4304734608	14151	Federal	Federal	GW	P
FED 22-30-10-18	30	100S	180E	4304734924	14280	Federal	Federal	GW	P
FEDERAL 43-30-9-19	30	090S	190E	4304735343	14202	Federal	Federal	GW	P
FED 11-22-9-19	22	090S	190E	4304735404	14203	Federal	Federal	GW	P
FED 42-21-9-19	21	090S	190E	4304735405	14928	Federal	Federal	GW	P
STATE 24-16-9-19	16	090S	190E	4304735588	14418	State	Federal	GW	P
FEDERAL 31-21-9-19	21	090S	190E	4304735606	14441	Federal	Federal	GW	P
FEDERAL 12-29-9-19	29	090S	190E	4304735614	14442	Federal	Federal	GW	P
FEDERAL 24-31-9-19	31	090S	190E	4304735623	14640	Federal	Federal	GW	P
FEDERAL 41-31-9-19	31	090S	190E	4304735624	14419	Federal	Federal	GW	P
LAMB TRUST 24-22-9-19	22	090S	190E	4304735732	14496	Fee	Fee	GW	P
LAMB TRUST 24-14-9-19	14	090S	190E	4304735733	14519	Fee	Fee	GW	P
FEDERAL 11-22-10-18	22	100S	180E	4304735808	15592	Federal	Federal	GW	P
FEDERAL 21-6-10-19	6	100S	190E	4304735844	14356	Federal	Federal	GW	P
DESERT SPRING ST 41-36-9-18	36	090S	180E	4304735845	14639	State	State	GW	P
STATE 12-32-9-19	32	090S	190E	4304735995	14871	State	State	GW	P
FEDERAL 12-20-9-19	20	090S	190E	4304736093	14976	Federal	Federal	GW	P
FEDERAL 32-20-9-19	20	090S	190E	4304736094	16120	Federal	Federal	GW	P
FEDERAL 23-30-9-19	30	090S	190E	4304736095	14872	Federal	Federal	GW	P
SHEEP WASH FED 34-26-9-18	26	090S	180E	4304736113	15096	Federal	Federal	GW	P
DESERT SPRING ST 23-36-9-18	36	090S	180E	4304736219	14738	State	State	GW	P
DESERT SPRING ST 21-36-9-18	36	090S	180E	4304736220	14763	State	State	GW	P
DESERT SPRING ST 12-36-9-18	36	090S	180E	4304736233	14764	State	State	GW	P
DESERT SPRING ST 43-36-9-18	36	090S	180E	4304736241	14992	State	State	GW	P
DESERT SPRING ST 34-36-9-18	36	090S	180E	4304736242	14716	State	State	GW	P
FEDERAL 14-31-9-19	31	090S	190E	4304736271	15884	Federal	Federal	GW	P
FEDERAL 12-31-9-19	31	090S	190E	4304736336	15086	Federal	Federal	GW	P
FEDERAL 21-31-9-19	31	090S	190E	4304736368	15605	Federal	Federal	GW	P
FEDERAL 23-31-9-19	31	090S	190E	4304736442	15715	Federal	Federal	GW	P
SHEEP WASH FED 43-25-9-18	25	090S	180E	4304736600	14977	Federal	Federal	GW	P
FEDERAL 43-19-9-19	19	090S	190E	4304736719	15186	Federal	Federal	GW	P

From: Gasco Production Company
To: Badlands Production Company
Effective Date: 4/16/2015

SHEEP WASH FED 21-25-9-18	25	090S	180E	4304736727	15475	Federal	Federal	GW	P
FEDERAL 21-30-9-19	30	090S	190E	4304736739	15476	Federal	Federal	GW	P
SHEEP WASH FED 23-25-9-18	25	090S	180E	4304736740	15213	Federal	Federal	GW	P
FEDERAL 23-19-9-19	19	090S	190E	4304736771	15355	Federal	Federal	GW	P
SHEEP WASH FED 41-25-9-18	25	090S	180E	4304736772	15338	Federal	Federal	GW	P
FEDERAL 41-30-9-19	30	090S	190E	4304736817	15212	Federal	Federal	GW	P
LAMB TRUST 34-22-9-19	22	090S	190E	4304736913	15187	Fee	Fee	GW	P
LAMB TRUST 14-14-9-19	14	090S	190E	4304736916	17012	Fee	Fee	GW	P
DESERT SPRING ST 33-36-9-18	36	090S	180E	4304737115	15011	State	State	GW	P
FEDERAL 14-17-9-19	17	090S	190E	4304737116	16163	Federal	Federal	GW	P
FEDERAL 34-18-9-19	18	090S	190E	4304737117	16275	Federal	Federal	GW	P
UTELAND ST 41-2-10-18	2	100S	180E	4304737132	15087	State	State	GW	P
UTELAND ST 43-2-10-18	2	100S	180E	4304737338	15365	State	State	GW	P
FEDERAL 41-19-9-19	19	090S	190E	4304737611	16311	Federal	Federal	GW	P
FEDERAL 32-30-9-19	30	090S	190E	4304737612	16051	Federal	Federal	GW	P
FEDERAL 12-30-9-19	30	090S	190E	4304737613	16052	Federal	Federal	GW	P
FEDERAL 21-19-9-19	19	090S	190E	4304737621	16253	Federal	Federal	GW	P
FEDERAL 14-18-9-19	18	090S	190E	4304737622	16264	Federal	Federal	GW	P
FEDERAL 34-30-9-19	30	090S	190E	4304737630	16557	Federal	Federal	GW	P
DESERT SPRING FED 21-1-10-18	1	100S	180E	4304737631	15961	Federal	Federal	GW	P
FEDERAL 12-1-10-18	1	100S	180E	4304737646	16023	Federal	Federal	GW	P
SHEEP WASH FED 14-25-9-18	25	090S	180E	4304737647	16121	Federal	Federal	GW	P
UTELAND ST 21-2-10-18	2	100S	180E	4304737676	16254	State	State	GW	P
UTELAND ST 12-2-10-18	2	100S	180E	4304737677	15806	State	State	GW	P
UTELAND ST 34-2-10-18	2	100S	180E	4304738028	16868	State	State	GW	P
FEDERAL 14-19-9-19	19	090S	190E	4304738336	16467	Federal	Federal	GW	P
FEDERAL 34-19-9-19	19	090S	190E	4304738337	16119	Federal	Federal	GW	P
SHEEP WASH FED 41-26-9-18	26	090S	180E	4304738351	16884	Federal	Federal	GW	P
SHEEP WASH FED 32-25-9-18	25	090S	180E	4304738352	16349	Federal	Federal	GW	P
SHEEP WASH FED 34-25-9-18	25	090S	180E	4304738353	16210	Federal	Federal	GW	P
FEDERAL 12-19-9-19	19	090S	190E	4304738407	16236	Federal	Federal	GW	P
SHEEP WASH FED 23-26-9-18	26	090S	180E	4304738465	16558	Federal	Federal	GW	P
SHEEP WASH FED 12-25-9-18	25	090S	180E	4304738469	16449	Federal	Federal	GW	P
FEDERAL 23-18-9-19	18	090S	190E	4304738575	16312	Federal	Federal	GW	P
LAMB TRUST 34-22A-9-19	22	090S	190E	4304738673	15832	Fee	Fee	GW	P
UTELAND FED 42-11-10-18	11	100S	180E	4304738896	16792	Federal	Federal	GW	P
STATE 21-32B	32	090S	190E	4304739170	16309	State	State	GW	P
STATE 22-32A	32	090S	190E	4304739171	16308	State	State	GW	P
STATE 21-32A	32	090S	190E	4304739172	16310	State	State	GW	P
FEDERAL 11-19-9-19	19	090S	190E	4304739717	17054	Federal	Federal	GW	P
SHEEP WASH FED 31-25-9-18	25	090S	180E	4304739729	17241	Federal	Federal	GW	P
SHEEP WASH FED 11-25-9-18	25	090S	180E	4304739730	17266	Federal	Federal	GW	P
DESERT SPG FED 41-1-10-18	1	100S	180E	4304739773	17013	Federal	Federal	GW	P
FED 32-19X-9-19(RIGSKID)	19	090S	190E	4304740233	17014	Federal	Federal	GW	P
FEDERAL 23-30G-9-19	30	090S	190E	4304751280	18211	Federal	Federal	OW	P
FEDERAL 34-19G-9-19	19	090S	190E	4304751281	18210	Federal	Federal	OW	P
FEDERAL 442-30-9-19	30	090S	190E	4304752870	19647	Federal	Federal	GW	P
FEDERAL 333-30-9-19	30	090S	190E	4304752872	19648	Federal	Federal	GW	P
FEDERAL 423-30-9-19	30	090S	190E	4304753011	19649	Federal	Federal	GW	P
Desert Springs State 412-36-9-18	36	090S	180E	4304753324	19783	State	State	GW	P
Desert Springs State 424-36-9-18	36	090S	180E	4304753325	19783	State	State	GW	P
Desert Springs State 133-36-9-18	36	090S	180E	4304753326	19747	State	State	GW	P
Desert Spring State 142-36-9-18	36	090S	180E	4304753327	19747	State	State	GW	P
DESERT SPRINGS ST 422-36-9-18	36	090S	180E	4304753328	19783	State	State	GW	P
WILKIN RIDGE ST 31-32-10-17	32	100S	170E	4301332677	15144	State	State	GW	S
RBW 4-11D	11	100S	180E	4304730718	16269	Federal	Federal	OW	S

From: Gasco Production Company
 To: Badlands Production Company
 Effective Date: 4/16/2015

RBU 2-11D	11	100S	180E	4304730826	16270	Federal	Federal	OW	S
RBU 6-11D	11	100S	180E	4304731192	16271	Federal	Federal	OW	S
STATE 2-32B	32	090S	190E	4304732221	11371	State	State	GW	S
STATE 9-36A	36	090S	180E	4304732225	11364	State	State	GW	S
FEDERAL 13-30B	30	090S	190E	4304733581	13249	Federal	Federal	GW	S
STATE 13-36A	36	090S	180E	4304733598	17838	State	State	GW	S
FEDERAL 16-26A	26	090S	180E	4304733601	12928	Federal	Federal	GW	S
FEDERAL 31-29	29	090S	190E	4304733653	13077	Federal	Federal	GW	S
RBU 1-10D	10	100S	180E	4304734312	16265	Federal	Federal	OW	S
FEDERAL 13-18-9-19	18	090S	190E	4304739776	17149	Federal	Federal	GW	S

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-76482
2. NAME OF OPERATOR: Gasco Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 7979 E. Tufts Ave. CITY Denver STATE CO ZIP 80237		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (303) 483-0044		8. WELL NAME and NUMBER: Desert Spring Fed 21-1-10-18
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0633 FNL 1512 FWL		9. API NUMBER: 4304737631
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 1 10S 18E S		10. FIELD AND POOL, OR WILDCAT: Uteland Butte

COUNTY: Uintah

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 4/16/2015	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Gasco Production Company requests a change of operator on this well, in addition to the wells on the attached list from Gasco Production Company to Badlands Production Company, effective date of 4/16/2015.

Gasco Production Company
7979 E Tufts Ave, Suite 1150
Denver CO 80237
303-996-1805

Michael Decker, Exec. Vice President & COO

Badlands Production Company
7979 E Tufts Ave, Suite 1150
Denver CO 80237
303-996-1805

Michael Decker, Exec. Vice President & COO

RECEIVED

JUN 02 2015

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Lindsey Cooke	TITLE Engineering Tech
SIGNATURE <i>Lindsey Cooke</i>	DATE 5/18/2015

(This space for State use only)

APPROVED

JAN 22 2016

DIV. OIL GAS & MINING
BY: *Rachel Medina*

Well Name	Section	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
FEDERAL 332-30-9-19	30	090S	190E	4304753012	19650	Federal	Federal	GW	DRL
WILKIN RIDGE FED 43-29-10-17	29	100S	170E	4301333098	15941	Federal	Federal	GW	OPS
LAMB TRUST 11-23-9-19	23	090S	190E	4304736915	16556	Fee	Fee	GW	OPS
SHEEP WASH FED 43-26-9-18	26	090S	180E	4304738573	17201	Federal	Federal	GW	OPS
FEDERAL 13-19-9-19	19	090S	190E	4304739777	18344	Federal	Federal	GW	OPS
FEDERAL 12-17-9-19	17	090S	190E	4304739800	17202	Federal	Federal	GW	OPS
GATE CYN 31-21-11-15	21	110S	150E	4301332391	13787	State	State	GW	P
WILKIN RIDGE ST 12-32-10-17	32	100S	170E	4301332447	14033	State	State	GW	P
GATE CYN 41-20-11-15	20	110S	150E	4301332475	14417	State	State	GW	P
WILKIN RIDGE FED 34-17-10-17	17	100S	170E	4301332560	14726	Federal	Federal	GW	P
GATE CYN 41-19-11-16	19	110S	160E	4301332611	14439	Federal	Federal	GW	P
WILKIN RIDGE ST 44-32-10-17	32	100S	170E	4301332619	15649	State	State	GW	P
WILKIN RIDGE FED 12-4-11-17	4	110S	170E	4301332674	15537	Federal	Federal	GW	P
WILKIN RIDGE ST 24-32-10-17	32	100S	170E	4301332676	15242	State	State	GW	P
WILKIN RIDGE FED 23-29-10-17	29	100S	170E	4301332679	14033	Federal	Federal	GW	P
GATE CYN ST 23-16-11-15	16	110S	150E	4301332685	16082	State	State	GW	P
WILKIN RIDGE ST 34-16-10-17	16	100S	170E	4301332730	15243	State	State	GW	P
WILKIN RIDGE FED 31-29-10-17	29	100S	170E	4301332773	15370	Federal	Federal	GW	P
WILKIN RIDGE 32-08	8	110S	170E	4301332778	14802	Federal	Federal	GW	P
GATE CYN ST 23-16-11-16	16	110S	160E	4301332888	15098	State	State	GW	P
WILKIN RIDGE FED 24-20-10-17	20	100S	170E	4301333081	15714	Federal	Federal	GW	P
WILKIN RIDGE FED 32-20-10-17	20	100S	170E	4301333087	15807	Federal	Federal	GW	P
WILKIN RIDGE FED 14-4-11-17	4	110S	170E	4301333099	15920	Federal	Federal	GW	P
RYE PATCH FED 22-21	22	110S	140E	4301333437	16919	Federal	Federal	GW	P
RYE PATCH FED 24-21	24	110S	140E	4301333443	16367	Federal	Federal	GW	P
RBUS 5-11D	11	100S	180E	4304730409	9005	Federal	Federal	OW	P
FEDERAL 7-25A	25	090S	180E	4304730624	9030	Federal	Federal	OW	P
RBUS 6-2D	2	100S	180E	4304731190	7075	State	State	OW	P
NGC 33-18J	18	090S	190E	4304731200	6155	Federal	Federal	OW	P
RBUS 13-2D	2	100S	180E	4304731280	16267	State	State	OW	P
RBUS 16-3D	3	100S	180E	4304731352	16268	Federal	Federal	OW	P
RBUS 10-11D	11	100S	180E	4304731357	7053	Federal	Federal	OW	P
RBUS 8-10D	10	100S	180E	4304731364	4955	Federal	Federal	OW	P
RBUS 15-3D	3	100S	180E	4304731539	9965	Federal	Federal	OW	P
RBUS 12-12D	12	100S	180E	4304731651	10688	Federal	Federal	OW	P
RBUS 2-10D	10	100S	180E	4304731801	10784	Federal	Federal	OW	P
RBUS 3-15D	15	100S	180E	4304733600	13213	Federal	Federal	OW	P
RBUS 3-12D	12	100S	180E	4304733739	14492	Federal	Federal	OW	P
STATE 7-36A	36	090S	180E	4304733741	14244	State	State	GW	P
FEDERAL 34-29	29	090S	190E	4304733750	13174	Federal	Federal	GW	P
FEDERAL 24-7 #1	7	100S	180E	4304733983	13182	Federal	Federal	GW	P
FEDERAL 23-29 #1	29	090S	190E	4304734111	13441	Federal	Federal	GW	P
FED 24-20-9-19	20	090S	190E	4304734168	14150	Federal	Federal	GW	P
FED 44-20-9-19	20	090S	190E	4304734169	14140	Federal	Federal	GW	P
FED 23-21-9-19	21	090S	190E	4304734199	13601	Federal	Federal	GW	P
FED 32-31-9-19	31	090S	190E	4304734201	13641	Federal	Federal	GW	P
FED 42-29-9-19	29	090S	190E	4304734202	13455	Federal	Federal	GW	P
PETES WASH 23-12 #1	12	100S	170E	4304734286	13492	Federal	Federal	GW	P
STATE 4-32B	32	090S	190E	4304734314	14440	State	State	GW	P
FED 14-18-2 #1	18	100S	180E	4304734539	13491	Federal	Federal	GW	P
FED 43-24-3 #1	24	100S	170E	4304734551	13726	Federal	Federal	GW	P
LYTHAM FED 22-22-9-19	22	090S	190E	4304734607	13640	Federal	Federal	GW	P
FED 11-21-9-19	21	090S	190E	4304734608	14151	Federal	Federal	GW	P
FED 22-30-10-18	30	100S	180E	4304734924	14280	Federal	Federal	GW	P
FEDERAL 43-30-9-19	30	090S	190E	4304735343	14202	Federal	Federal	GW	P
FED 11-22-9-19	22	090S	190E	4304735404	14203	Federal	Federal	GW	P
FED 42-21-9-19	21	090S	190E	4304735405	14928	Federal	Federal	GW	P
STATE 24-16-9-19	16	090S	190E	4304735588	14418	State	Federal	GW	P

FEDERAL 31-21-9-19	21	090S	190E	4304735606	14441	Federal	Federal	GW	P
FEDERAL 12-29-9-19	29	090S	190E	4304735614	14442	Federal	Federal	GW	P
FEDERAL 24-31-9-19	31	090S	190E	4304735623	14640	Federal	Federal	GW	P
FEDERAL 41-31-9-19	31	090S	190E	4304735624	14419	Federal	Federal	GW	P
LAMB TRUST 24-22-9-19	22	090S	190E	4304735732	14496	Fee	Fee	GW	P
LAMB TRUST 24-14-9-19	14	090S	190E	4304735733	14519	Fee	Fee	GW	P
FEDERAL 11-22-10-18	22	100S	180E	4304735808	15592	Federal	Federal	GW	P
FEDERAL 21-6-10-19	6	100S	190E	4304735844	14356	Federal	Federal	GW	P
DESERT SPRING ST 41-36-9-18	36	090S	180E	4304735845	14639	State	State	GW	P
STATE 12-32-9-19	32	090S	190E	4304735995	14871	State	State	GW	P
FEDERAL 12-20-9-19	20	090S	190E	4304736093	14976	Federal	Federal	GW	P
FEDERAL 32-20-9-19	20	090S	190E	4304736094	16120	Federal	Federal	GW	P
FEDERAL 23-30-9-19	30	090S	190E	4304736095	14872	Federal	Federal	GW	P
SHEEP WASH FED 34-26-9-18	26	090S	180E	4304736113	15096	Federal	Federal	GW	P
DESERT SPRING ST 23-36-9-18	36	090S	180E	4304736219	14738	State	State	GW	P
DESERT SPRING ST 21-36-9-18	36	090S	180E	4304736220	14763	State	State	GW	P
DESERT SPRING ST 12-36-9-18	36	090S	180E	4304736233	14764	State	State	GW	P
DESERT SPRING ST 43-36-9-18	36	090S	180E	4304736241	14992	State	State	GW	P
DESERT SPRING ST 34-36-9-18	36	090S	180E	4304736242	14716	State	State	GW	P
FEDERAL 14-31-9-19	31	090S	190E	4304736271	15884	Federal	Federal	GW	P
FEDERAL 12-31-9-19	31	090S	190E	4304736336	15086	Federal	Federal	GW	P
FEDERAL 21-31-9-19	31	090S	190E	4304736368	15605	Federal	Federal	GW	P
FEDERAL 23-31-9-19	31	090S	190E	4304736442	15715	Federal	Federal	GW	P
SHEEP WASH FED 43-25-9-18	25	090S	180E	4304736600	14977	Federal	Federal	GW	P
FEDERAL 43-19-9-19	19	090S	190E	4304736719	15186	Federal	Federal	GW	P
SHEEP WASH FED 21-25-9-18	25	090S	180E	4304736727	15475	Federal	Federal	GW	P
FEDERAL 21-30-9-19	30	090S	190E	4304736739	15476	Federal	Federal	GW	P
SHEEP WASH FED 23-25-9-18	25	090S	180E	4304736740	15213	Federal	Federal	GW	P
FEDERAL 23-19-9-19	19	090S	190E	4304736771	15355	Federal	Federal	GW	P
SHEEP WASH FED 41-25-9-18	25	090S	180E	4304736772	15338	Federal	Federal	GW	P
FEDERAL 41-30-9-19	30	090S	190E	4304736817	15212	Federal	Federal	GW	P
LAMB TRUST 34-22-9-19	22	090S	190E	4304736913	15187	Fee	Fee	GW	P
LAMB TRUST 14-14-9-19	14	090S	190E	4304736916	17012	Fee	Fee	GW	P
DESERT SPRING ST 33-36-9-18	36	090S	180E	4304737115	15011	State	State	GW	P
FEDERAL 14-17-9-19	17	090S	190E	4304737116	16163	Federal	Federal	GW	P
FEDERAL 34-18-9-19	18	090S	190E	4304737117	16275	Federal	Federal	GW	P
UTELAND ST 41-2-10-18	2	100S	180E	4304737132	15087	State	State	GW	P
UTELAND ST 43-2-10-18	2	100S	180E	4304737338	15365	State	State	GW	P
FEDERAL 41-19-9-19	19	090S	190E	4304737611	16311	Federal	Federal	GW	P
FEDERAL 32-30-9-19	30	090S	190E	4304737612	16051	Federal	Federal	GW	P
FEDERAL 12-30-9-19	30	090S	190E	4304737613	16052	Federal	Federal	GW	P
FEDERAL 21-19-9-19	19	090S	190E	4304737621	16253	Federal	Federal	GW	P
FEDERAL 14-18-9-19	18	090S	190E	4304737622	16264	Federal	Federal	GW	P
FEDERAL 34-30-9-19	30	090S	190E	4304737630	16557	Federal	Federal	GW	P
DESERT SPRING FED 21-1-10-18	1	100S	180E	4304737631	15961	Federal	Federal	GW	P
FEDERAL 12-1-10-18	1	100S	180E	4304737646	16023	Federal	Federal	GW	P
SHEEP WASH FED 14-25-9-18	25	090S	180E	4304737647	16121	Federal	Federal	GW	P
UTELAND ST 21-2-10-18	2	100S	180E	4304737676	16254	State	State	GW	P
UTELAND ST 12-2-10-18	2	100S	180E	4304737677	15806	State	State	GW	P
UTELAND ST 34-2-10-18	2	100S	180E	4304738028	16868	State	State	GW	P
FEDERAL 14-19-9-19	19	090S	190E	4304738336	16467	Federal	Federal	GW	P
FEDERAL 34-19-9-19	19	090S	190E	4304738337	16119	Federal	Federal	GW	P
SHEEP WASH FED 41-26-9-18	26	090S	180E	4304738351	16884	Federal	Federal	GW	P
SHEEP WASH FED 32-25-9-18	25	090S	180E	4304738352	16349	Federal	Federal	GW	P
SHEEP WASH FED 34-25-9-18	25	090S	180E	4304738353	16210	Federal	Federal	GW	P
FEDERAL 12-19-9-19	19	090S	190E	4304738407	16236	Federal	Federal	GW	P
SHEEP WASH FED 23-26-9-18	26	090S	180E	4304738465	16558	Federal	Federal	GW	P
SHEEP WASH FED 12-25-9-18	25	090S	180E	4304738469	16449	Federal	Federal	GW	P
FEDERAL 23-18-9-19	18	090S	190E	4304738575	16312	Federal	Federal	GW	P

LAMB TRUST 34-22A-9-19	22	090S	190E	4304738673	15832	Fee	Fee	GW	P
UTELAND FED 42-11-10-18	11	100S	180E	4304738896	16792	Federal	Federal	GW	P
STATE 21-32B	32	090S	190E	4304739170	16309	State	State	GW	P
STATE 22-32A	32	090S	190E	4304739171	16308	State	State	GW	P
STATE 21-32A	32	090S	190E	4304739172	16310	State	State	GW	P
FEDERAL 11-19-9-19	19	090S	190E	4304739717	17054	Federal	Federal	GW	P
SHEEP WASH FED 31-25-9-18	25	090S	180E	4304739729	17241	Federal	Federal	GW	P
SHEEP WASH FED 11-25-9-18	25	090S	180E	4304739730	17266	Federal	Federal	GW	P
DESERT SPG FED 41-1-10-18	1	100S	180E	4304739773	17013	Federal	Federal	GW	P
FED 32-19X-9-19(RIGSKID)	19	090S	190E	4304740233	17014	Federal	Federal	GW	P
FEDERAL 23-30G-9-19	30	090S	190E	4304751280	18211	Federal	Federal	OW	P
FEDERAL 34-19G-9-19	19	090S	190E	4304751281	18210	Federal	Federal	OW	P
FEDERAL 442-30-9-19	30	090S	190E	4304752870	19647	Federal	Federal	GW	P
FEDERAL 333-30-9-19	30	090S	190E	4304752872	19648	Federal	Federal	GW	P
FEDERAL 423-30-9-19	30	090S	190E	4304753011	19649	Federal	Federal	GW	P
Desert Springs State 412-36-9-18	36	090S	180E	4304753324	19783	State	State	GW	P
Desert Springs State 424-36-9-18	36	090S	180E	4304753325	19783	State	State	GW	P
Desert Springs State 133-36-9-18	36	090S	180E	4304753326	19747	State	State	GW	P
Desert Spring State 142-36-9-18	36	090S	180E	4304753327	19747	State	State	GW	P
DESERT SPRINGS ST 422-36-9-18	36	090S	180E	4304753328	19783	State	State	GW	P
WILKIN RIDGE ST 31-32-10-17	32	100S	170E	4301332677	15144	State	State	GW	S
SQUAW CROSSING U 5	2	100S	180E	4304730129	16266	State	State	OW	S
RBW 4-11D	11	100S	180E	4304730718	16269	Federal	Federal	OW	S
RBW 2-11D	11	100S	180E	4304730826	16270	Federal	Federal	OW	S
RBW 6-11D	11	100S	180E	4304731192	16271	Federal	Federal	OW	S
STATE 2-32B	32	090S	190E	4304732221	11371	State	State	GW	S
STATE 9-36A	36	090S	180E	4304732225	11364	State	State	GW	S
FEDERAL 13-30B	30	090S	190E	4304733581	13249	Federal	Federal	GW	S
STATE 13-36A	36	090S	180E	4304733598	17838	State	State	GW	S
FEDERAL 16-26A	26	090S	180E	4304733601	12928	Federal	Federal	GW	S
FEDERAL 31-29	29	090S	190E	4304733653	13077	Federal	Federal	GW	S
RBW 1-10D	10	100S	180E	4304734312	16265	Federal	Federal	OW	S
FEDERAL 13-18-9-19	18	090S	190E	4304739776	17149	Federal	Federal	GW	S